
# SITE PLAN & LOT LINE COMBINATION FOR DAVIDSON DRIVE HOLDINGS, LLC LAKE STATION ROAD TOWN OF CHESTER, ORANGE COUNTY, NY.



LOCATION MAP SCALE: 1"=400' SOURCE: TAX MAPS

TAX MAP NUMBER

SECTION: 17

BLOCK: 1

LOT: 22.1, 22.2, 22.3, 22.4, 22.5, 22.6, 22.7, 22.8

DEED REFERENCE

LIBER: 14568

PAGE: 351

TOTAL TRACT AREA

699,971± S.F.

= 16.07± ACRES

OWNER & APPLICANT


DAVIDSON DRIVE HOLDINGS, LLC
99 FOREST ROAD UNIT 103
MONROE, NY 10950


GENERAL NOTES:

HOURS OF OPERATION: 8AM-6PM DAILY EXCEPT FOR NATIONAL HOLIDAYS. ADDITIONAL WORK SHIFTS REQUIRE PLANNING BOARD APPROVAL.
 THE PROJECT WILL NOT UTILIZE ANY PESTICIDES OR HERBICIDES ON THE SITE AND WILL NOT INCLUDE BULK STORAGE OF PETROLEUM, OTHER CHEMICALS OR ANY HAZARDOUS WASTE.
 THE USE OF ENGINE BRAKES WITHIN THE PROJECT SITE IS PROHIBITED.

RAWING	LIST

CUEET !	OUEST TITLE	ODIOINIAL DATE / LACT DEVICES SATE
-	SHEET TITLE	ORIGINAL DATE / LAST REVISED DATE
01 OF 22	TITLE SHEET	03-21-22 / 11-13-23
02 OF 22	EXISTING CONDITIONS MAP	03-21-22 / 11-13-23
03 OF 22	SLOPE ANALYSIS	03-21-22 / 11-13-23
04 OF 22	SITE PLAN	03-21-22 / 11-13-23
05 OF 22	GRADING & UTILITY PLAN	03-21-22 / 11-13-23
06 OF 22	DRIVEWAY PROFILES	03-21-22 / 11-13-23
07 OF 22	SECTION A-A	03-21-22 / 11-13-23
08 OF 22	DRAINAGE PROFILES 1	03-21-22 / 11-13-23
09 OF 22	DRAINAGE PROFILES 2	03-21-22 / 11-13-23
10 OF 22	EROSION AND SEDIMENT CONTROL PLAN	03-21-22 / 11-13-23
11 OF 22	EROSION AND SEDIMENT CONTROL DETAILS	03-21-22 / 11-13-23
12 OF 22	LIGHTING PLAN	03-21-22 / 11-13-23
13 OF 22	LANDSCAPING PLAN	03-21-22 / 11-13-23
14 OF 22	LANDSCAPING DETAILS	03-21-22 / 11-13-23
15 OF 22	TRUCK TURNING DIAGRAM - WB67	03-21-22 / 11-13-23
16 OF 22	TRUCK TURNING DIAGRAM - WB67	03-21-22 / 11-13-23
17 OF 22	TRUCK TURNING DIAGRAM - WB67	03-21-22 / 11-13-23
18 OF 22	FIRETRUCK TURNING DIAGRAMS	03-21-22 / 11-13-23
19 OF 22	SDS DETAILS	03-21-22 / 11-13-23
20 OF 22	CONSTRUCTION DETAILS	03-21-22 / 11-13-23
21 OF 22	STORMWATER CONSTRUCTION DETAILS	03-21-22 / 11-13-23
22 OF 22	HABITAT PROTECTION PLAN	03-21-22 / 11-13-23





COPYRIGHT 2021, ARDEN CONSULTING ENGINEERS, P.L.L.C. - ALL RIGHTS RESERVED

TITLE SHEET

9. MM 11/13/23 PER PH & PB COMMENTS

8. MM 8/7/23 SITE RE-DESIGN

7. MM 2/6/23 PH CONSULTANT COMMENTS

6. MM 1/17/23 PUBLIC HEARING COMMENTS

5. MM 3/21/22 DEC EMAIL DATED 03/11/22

4. MM 12/2/21 PER PB MTG & AF COMMENT LETTER


3. MM 9/16/21 PREPARATION OF PRELIMINARY PLANS

2. MM 5/19/21 REVISION PER PB MTG. & COMMENT LETTERS

1. MM 3/23/21 ROAD LAYOUT REVISION PER PB MTG.

THIS SHEET IS NOT VALID WITHOUT ALL OF THE SHEETS THAT COMPRISE THE SE

# ARDEN CONSULTING ENGINEERS, PLLC P.O. BOX 340 MONROE, N.Y. T: 845-782-8114 E: MAM@ARDENCONSULTING.NET



LIC. NO. 78577

SITE PLAN & LOT LINE COMBINATION FOR
DAVIDSON DRIVE HOLDINGS, LLC
LAKE STATION ROAD
TOWN OF CHESTER, COUNTY OF ORANGE, NY

TITLE SHEET

CHECKED:


WARNING— IT IS A VIOLATION OF NEW YORK EDUCATIONAL LAW, SECTION 7209.2, FOR ANY PERSON, UNLESS ACTING UNDER THE DIRECTION OF A LICENSED PROFESSIONAL ENGINEER OR LAND SURVEYOR, TO ALTER THIS DOCUMENT IN ANY WAY. IF ALTERED, THE ALTERING PERSON SHALL COMPLY WITH THE REQUIREMENTS OF NEW YORK EDUCATIONAL LAW, SECTION 7209.2


ONLY MAPS WITH EMBOSSED SEALS ARE GENUINE COPIES OF THE ORIGINAL WORK AND OPINION. MAPS NOT BEARING


EMBOSSED SEALS SHOULD NOT BE RELIED UPON SINCE OTHER


THAN EMBOSSED—SEAL COPIES MAY CONTAIN UNAUTHORIZED AND UNDETECTABLE MODIFICATIONS, DELETIONS, ADDITIONS


ND CHANGES.











DRIVEWAY PROFILE

HORIZONTAL SCALE: 1"=20'

VERTICAL SCALE; 1"=2'

WARNING— IT IS A VIOLATION OF NEW YORK EDUCATIONAL LAW, SECTION 7209.2, FOR ANY PERSON, UNLESS ACTING UNDER THE DIRECTION OF A LICENSED PROFESSIONAL ENGINEER OR LAND SURVEYOR, TO ALTER THIS DOCUMENT IN ANY WAY. IF ALTERED, THE ALTERING PERSON SHALL COMPLY WITH THE REQUIREMENTS OF NEW YORK EDUCATIONAL LAW, SECTION 7209.2

ONLY MAPS WITH EMBOSSED SEALS ARE GENUINE COPIES OF THE ORIGINAL WORK AND OPINION. MAPS NOT BEARING EMBOSSED SEALS SHOULD NOT BE RELIED UPON SINCE OTHER THAN EMBOSSED—SEAL COPIES MAY CONTAIN UNAUTHORIZED AND UNDETECTABLE MODIFICATIONS, DELETIONS, ADDITIONS AND CHANGES.


TOWN OF CHESTER PLANNING BOARD APPROVAL

COPYRIGHT 2021, ARDEN CONSULTING ENGINEERS, P.L.L.C. — ALL RIGHTS RESERVED LIC. NO. 78577

REVISION	BY	DATE	DESCRIPTION
9.	ММ	11/13/23	PER PH & PB COMMENTS
8.	ММ	8/7/23	SITE RE-DESIGN
7.	ММ	2/6/23	PH CONSULTANT COMMENTS
6.	ММ	1/17/23	PUBLIC HEARING COMMENTS
5.	ММ	3/21/22	DEC EMAIL DATED 03/11/22
4.	ММ	12/2/21	PER PB MTG & AF COMMENT LETTER
3.	ММ	9/16/21	PREPARATION OF PRELIMINARY PLANS
2.	ММ	5/19/21	REVISION PER PB MTG. & COMMENT LETTERS
1.	ММ	3/23/21	ROAD LAYOUT REVISION PER PB MTG.
THIS S	HEET IS	S NOT V	ALID WITHOUT ALL OF THE SHEETS THAT COMPRISE THE SET

# ARDEN CONSULTING ENGINEERS, PLLC

P.O. BOX 340 MONROE, N.Y. T: 845-782-8114 E: MAM@ARDENCONSULTING.NET




LAKE STATION ROAD TOWN OF CHESTER, COUNTY OF ORANGE, NY

O3-21-22
DRAWN:

MM
CHECKED:

MM
SHEET NO.
06 OF 22

DRIVEWAY PROFILES



TOWN OF CHESTER PLANNING BOARD APPROVAL

	REVISION	BY	DATE	DESCRIPTION
	9.	ММ	11/13/23	PER PH & PB COMMENTS
	8.	ММ	8/7/23	SITE RE-DESIGN
	7.	ММ	2/6/23	PH CONSULTANT COMMENTS
	6.	ММ	1/17/23	PUBLIC HEARING COMMENTS
	5.	ММ	3/21/22	DEC EMAIL DATED 03/11/22
	4.	ММ	12/2/21	PER PB MTG & AF COMMENT LETTER
	3.	ММ	9/16/21	PREPARATION OF PRELIMINARY PLANS
	2.	ММ	5/19/21	REVISION PER PB MTG. & COMMENT LETTERS
	1.	ММ	3/23/21	ROAD LAYOUT REVISION PER PB MTG.
•	THIS S	HEET IS	NOT V	ALID WITHOUT ALL OF THE SHEETS THAT COMPRISE THE SET

# ARDEN CONSULTING ENGINEERS, PLLC P.O. BOX 340 MONROE, N.Y.

T: 845-782-8114 E: MAM@ARDENCONSULTING.NET

SITE PLAN & LOT LINE COMBINATION FOR DAVIDSON DRIVE HOLDINGS, LLC LAKE STATION ROAD TOWN OF CHESTER, COUNTY OF ORANGE, NY


SECTION A-A


MM
CHECKED:


MM
SHEET NO.
07 OF 22

COPYRIGHT 2021, ARDEN CONSULTING ENGINEERS, P.L.L.C. — ALL RIGHTS RESERVED


MICHAEL A. MORGANTE, P.E.
LIC. NO. 78577









DRAINAGE PLAN #2 SCALE: 1"=40'



DRAINAGE PROFILES #2 HORIZONTAL SCALE: 1"=40'
VERTICAL SCALE: 1"=4'



DRAINAGE PLAN #3
scale: 1"=40"




DRAINAGE PROFILES #3
HORIZONTAL SCALE: 1"=40" VERTICAL SCALE: 1"=4"

	Ī	1	
REVISION	BY	DATE	DESCRIPTION
8.	ММ	11/13/23	PER PH & PB COMMENTS
7.	ММ	8/7/23	SITE RE-DESIGN
6.	ММ	2/6/23	PH CONSULTANT COMMENTS
5.	ММ	1/17/23	PUBLIC HEARING COMMENTS
4.	ММ	3/21/22	DEC EMAIL DATED 03/11/22
3.	ММ	9/16/21	PREPARATION OF PRELIMINARY PLANS
2.	ММ	5/19/21	REVISION PER PB MTG. & COMMENT LETTERS
1.	ММ	3/23/21	ROAD LAYOUT REVISION PER PB MTG.
THIS S	SHEET IS	S NOT V	ALID WITHOUT ALL OF THE SHEETS THAT COMPRISE THE SE

# ARDEN CONSULTING ENGINEERS, PLLC

P.O. BOX 340 MONROE, N.Y. T: 845-782-8114 E: MAM@ARDENCONSULTING.NET




SITE PLAN & LOT LINE COMBINATION FOR DAVIDSON DRIVE HOLDINGS, LLC LAKE STATION ROAD TOWN OF CHESTER, COUNTY OF ORANGE, NY


MM CHECKED:

DRAINAGE PROFILES 1

MICHAEL A. MORGANTE, P.E. LIC. NO. 78577

COPYRIGHT 2021, ARDEN CONSULTING ENGINEERS, P.L.L.C. - ALL RIGHTS RESERVED





BEST MANAGEMENT PRACTICES FOR SITE FACILITY MAINTENANCE

THE OWNER WILL BE RESPONSIBLE FOR THE MAINTENANCE AND OPERATION OF ALL SITE RELATED FACILITIES, INCLUDING THE STORM WATER SEDIMENT AND DETENTION BASINS AND THE FOLLOWING MEASURES AND/OR STRUCTURES, AS APPLICABLE AND SHOWN ON THE PLANS:

WATER QUALITY INLETS

1. WATER QUALITY INLETS SHALL BE CLEANED OUT AT LEAST TWICE A YEAR TO REMOVE POLLUTANTS. REMOVED MATERIAL SHOULD BE TAKEN TO A TREATMENT PLANT OR APPROVED LANDFILL FOR DISPOSAL.

2. STORM WATER INLETS THROUGHOUT THE SITE SHALL BE INSPECTED ANNUALLY FOR ACCUMULATED SEDIMENT OR OTHER PROBLEMS AND REPAIRED AS NECESSARY.

PARKING AND ROADWAY PAVEMENTS

1. PARKING AREA AND ROADWAY PAVEMENTS SHALL BE SWEPT ON A REGULAR BASIS TO REMOVE ACCUMULATED SEDIMENT.

COLLECTED SEDIMENT SHALL BE REMOVED TO AN APPROVED DISPOSAL SITE WHICH WILL NOT ALLOW THE RE-ENTRANCE OF SILT INTO THE STORM WATER DRAINAGE SYSTEM.

VEGETATIVE STABILIZATION

1. ALL VEGETATIVE PLANTING ON AREAS WHICH HAVE BEEN DISTURBED AND ARE FINISH GRADED SHALL BE INSPECTED AFTER EACH RAIN EVENT. PLANTING (OR SEEDING) SHALL BE MAINTAINED IN A VIABLE CONDITION TO STABILIZE THE SOIL AND TO PREVENT SOIL EROSION. RESTORE ALL SITE PLANTING AND/OR SEEDING WHICH HAS BEEN DAMAGED TO A VIABLE CONDITION.

2. IF VEGETATIVE STABILIZATION HAS BEEN DAMAGED FROM STORM WATER EROSION, CORRECT UPSTREAM CONDITIONS WHICH CAUSED THE EROSION. CHECK DAMS MAY BE REQUIRED IN DRAINAGE WAYS, AND STONE OUTFALL APRONS MAY BE REQUIRED TO BE REPAIRED AT STORM WATER OUTLETS.

CONSTRUCTION ACTIVITY
1. CONSTRUCTION ACTIVITIES WILL OCCUR DURING WEEKDAYS COMMENCING AT 7:00 AM AND TERMINATING AT 6:00 PM

EROSION AND SILTATION CONTROL NOTES:

1. GRADED AREAS — UPPER ELEVATIONS: PROVIDE TEMPORARY DRAINAGE SWALES, 1% GRADE MIN., TO DIRECT RUNOFF AWAY FROM CONSTRUCTION SITES. DISCHARGE AREAS AND ENERGY DISPERSION REQUIREMENTS TO BE ACCEPTABLE TO OWNER.

2. GRADED AREAS — LOWER ELEVATIONS: PROVIDE DRAINAGE SWALES, 1% MIN. GRADES, WITH STAKED AND SECURED HAY BALE BERMS TO PREVENT DOWN STREAM AND DOWN GRADIENT SILTATION.

SEDIMENT & EROSION CONTROL NOTES & CONSTRUCTION SEQUENCING

1. CONSTRUCT STABILIZED CONSTRUCTION ENTRANCES FOR ALL ROAD AND DRIVE ENTRANCES. STREETS SHALL BE CLEANED

DAILY.

2. INSTALL SEDIMENT BARRIERS/SWALES/DITCHES/DIKES AT DOWN SLOPE AREAS FROM ALL PROPOSED GRADING OPERATIONS, AND INSTALL OTHER SEDIMENTATION AND EROSION CONTROL STRUCTURES OR MEASURES AS SHOWN ON THE DRAWINGS.

3. LAND DISTURBANCE SHALL BE LIMITED TO ONLY THAT AREA NECESSARY FOR DEVELOPMENT. NO MORE THAN FIVE (5) ACRES OF UNPROTECTED SOIL SHALL BE DISTURBED AT ONE TIME. PREVIOUS EARTHWORK SHALL BE STABILIZED AS SPECIFIED BEFORE ADDITIONAL AREA IS EXPOSED. EXISTING DWELLINGS AND STRUCTURES SHALL BE REMOVED PRIOR TO ANY SITE CLEARING AND SOIL DISTURBANCE.

4. CLEAR EXISTING TREES AND VEGETATION FROM AREAS TO BE EXCAVATED OR FILLED, THEN STRIP AND STOCKPILE TOPSOIL FROM ALL AREAS TO BE DISTURBED. SEED STOCKPILED TOPSOIL WITH TEMPORARY RYEGRASS COVER AS SPECIFIED BELOW

(SEE NOTE 8), AND ERECT A SILT FENCE AROUND THE STOCKPILE.

5. PROTECT ALL TREES WHICH ARE TO REMAIN AND WHICH ARE IN OR NEAR CONSTRUCTION AREAS.

6. PERFORM NECESSARY EXCAVATION OR FILL OPERATIONS TO BRING SITE TO DESIRED SUBGRADE.

7. INSTALL SEDIMENT BARRIERS AROUND ALL STORM DRAIN INLETS, OR MODIFY SEDIMENT CONTROL MEASURES INSTALLED IN #2 ABOVE AND MAINTAIN UNTIL ALL DISTURBED AREAS ARE STABILIZED WITH VEGETATION AND ALL PAVEMENTS ARE PAVED WITH A BASE COURSE.

8. TEMPORARILY SEED ALL DISTURBED AREAS WHICH WILL REMAIN UNDISTURBED FOR A PERIOD OF 15 DAYS OR MORE AND WHICH WILL NOT BE UNDER CONSTRUCTION WITHIN 30 DAYS IN ACCORDANCE WITH SPECIFICATION FOR VEGETATIVE ESTABLISHMENT.

9. IF CONSTRUCTION IS SUSPENDED OR COMPLETED, ALL DISTURBED AREAS SHALL BE SEEDED AND MULCHED IMMEDIATELY. ALL SLOPES STEEPER THAN ONE ON THREE (V/H) AND PERIMETER TRENCHES AND TRAP EMBANKMENTS SHALL, ON COMPLETION, BE IMMEDIATELY STABILIZED WITH TEMPORARY SEEDING AND MULCHING.

10. AFTER COMPLETION OF SITE CONSTRUCTION, FINE GRADE AND SPREAD TOPSOIL ON ALL LAWN AREAS AND SEED WITH PERMANENT LAWN MIX AS DISCUSSED ON THE SPECIFICATIONS FOR FOR VEGETATIVE ESTABLISHMENT ON THIS SHEET.

11. DURING THE PROGRESS OF CONSTRUCTION, MAINTAIN ALL SEDIMENT TRAPS, BARRIERS, AND FILTERS AS NECESSARY TO PREVENT THEIR BEING CLOGGED UP WITH SEDIMENT.

12. AFTER PAVEMENTS ARE INSTALLED AND PERMANENT VEGETATIVE COVER AND PLANTINGS ARE ESTABLISHED, REMOVE SEDIMENT BARRIERS AND SEED THOSE DISTURBED AREAS.

13. MAINTAIN ALL SEEDED AND PLANTED AREAS TO INSURE A VIABLE STABILIZED VEGETATIVE COVER.

14. STRUCTURAL MEASURES MUST BE MAINTAINED TO BE EFFECTIVE. IN GENERAL, THESE MEASURES MUST BE PERIODICALLY INSPECTED TO INSURE STRUCTURAL INTEGRITY, TO DETECT VANDALISM DAMAGE, AND FOR CLEANING AND REPAIR WHENEVER NECESSARY.

15. DURING CONSTRUCTION, ALL STRUCTURES SHOULD BE INSPECTED WEEKLY AND AFTER EVERY RAIN, REMOVE ACCUMULATE.

NECESSARY.

15. DURING CONSTRUCTION, ALL STRUCTURES SHOULD BE INSPECTED WEEKLY AND AFTER EVERY RAIN. REMOVE ACCUMULATED SEDIMENT AND STOCKPILE AND STABILIZE IN AN AREA NOT SUBJECT TO FURTHER EROSION.

16. AFTER CONSTRUCTION IS COMPLETED, PERMANENT SEDIMENT OR EROSION CONTROL STRUCTURES SHOULD BE INSPECTED AT LEAST SEMI—ANNUALLY AND AFTER EVERY RAIN.

SPECIFICATIONS FOR VEGETATIVE ESTABLISHMENT:

A. SEEDBED PREPARATION: AREA TO BE SEEDED SHALL BE LOOSE AND FRIABLE TO A DEPTH OF AT LEAST 3 INCHES. THE TOP LAYER SHALL BE LOOSENED BY RAKING, DISKING OR OTHER ACCEPTABLE MEANS BEFORE SEEDING OCCURS. FOR SITES LESS THAN 5 ACRES, APPLY 100 POUNDS OF DOLOMITIC LIMESTONE AND 21 POUNDS OF 10-20-20 FERTILIZER PER 1,000 SF. HARROW OR DISK LIME AND FERTILIZER INTO THE SOIL TO A DEPTH OF AT LEAST 3 INCHES ON SLOPES FLATTER THAN 3:1. B. SEEDING: APPLY 5-6 POUNDS PER 1,000 SF OF SEED MIX BETWEEN FEBRUARY 1 AND MAY 15 OR BETWEEN AUGUST 15 AND OCTOBER 31. APPLY SEED UNIFORMLY ON A MOIST FIRM SEEDBED WITH A CYCLONE SEEDED DRILL, CULTIPACKR SEEDER OR HYDROSEEDER (SLURRY INCLUDES SEEDS AND FERTILIZER, RECOMMENDED ON STEEP SLOPES ONLY). MAXIMUM SEED DEPTH SHOULD BE 1/4 INCH IN CLAYEY SOILS AND 1/2 INCH IN SANDY SOILS WHEN USING OTHER THAN THE HYDROSEEDER METHOD. IRRIGATE IF SOIL MOISTURE IS DEFICIENT TO SUPPORT ADEQUATE GROWTH UNTIL VEGETATION IS FIRMLY ESTABLISHED. SELECT SEED MIXTURES FROM SECTION 3, NYS GUIDELINES FOR URBAN EROSION & SEDIMENT CONTROL. C. MULCHING: MULCH SHALL BE APPLIED TO ALL SEEDED AREAS IMMEDIATELY AFTER SEEDING. DURING THE TIME PERIODS WHEN SEEDING IS NOT PERMITTED, MULCH SHALL BE APPLIED IMMEDIATELY AFTER GRADING. MULCH SHALL BE UNROTTED, UNCHOPPED, SMALL GRAIN STRAW APPLIED AT A RATE OF 2 TONS PER ACRE OR 90 POUNDS PER 1,000 SQUARE FEET (2 BALES). IF A MULCH ANCHORING TOOL IS USED, APPLY 2.5 TONS PER ACRE. MULCH MATERIALS SHALL BE RELATIVELY FREE OF ALL KINDS OF WEEDS AND SHALL BE COMPLETELY FREE OF PROHIBITED NOXIOUS WEEDS. SPREAD MULCH UNIFORMLY, MECHANICALLY, OR BY HAND TO A DEPTH OF 1-2 INCHES. D. SECURING STRAW MULCH: STRAW MULCH SHALL BE SECURED IMMEDIATELY FOLLOWING MULCH APPLICATIONS TO MIMIMIZE MOVEMENT OF WIND OR WATER. THE FOLLOWING METHODS ARE USE A MULCH ANCHORING TOOL WHICH IS DESIGNED TO PUNCH AND ANCHOR FABRIC TYPE MULCH INTO THE SOIL SURFACE TO A MINIMUM DEPTH OF 2 INCHES. THIS IS THE MOST EFFECTIVE METHOD FOR SECURING MULCH, HOWEVER, IT IS LIMITED TO RELATIVELY FLAT AREAS WHERE EQUIPMENT CAN OPERATE SAFELY. ii. WOOD CELLULOSE FIBER MAY BE USED FOR ANCHORING STRAW. APPLY THE FIBER BINDER AT A NET DRY WEIGHT OF 750 POUNDS PER ACRE. IF MIXED WITH WATER, USE 50 POUNDS OF WOOD CELLULOSE FIBER PER 100 GALLONS OF WATER. iii. LIQUID BINDERS MAY BE USED AND APPLIED HEAVIER AT THE EDGES WHERE WIND CATCHES MULCH, SUCH AS IN VALLEYS AND ON CRESTS OF SLOPES. THE REMAINDER OF THE AREA SHOULD APPEAR UNIFORM AFTER BINDER APPLICATION. iv. LIGHTWEIGHT NETTING, MAY BE USED TO SECURE MULCH. THE NETTING WILL BE STAPLED TO THE GROUND ACCORDING TO MANUFACTURERS' RECOMMENDATIONS.

# 2. TEMPORARY SEEDING: LIME: 100 POUNDS OF DOLOMITIC LIMESTONE PER 1,000 SF FERTILIZER: 15 POUNDS OF 10-10-10 PER 1,000 SF

SEED: PERENNIAL RYE-0.92 POUNDS PER 1,000 SF

3. FILL:
NO FILLS MAY BE PLACED ON FROZEN GROUND. ALL FILL TO BE PLACED IN APPROXIMATELY HORIZONTAL LAYERS, EACH LAYER HAVING A LOOSE THICKNESS OF NOT MORE THAN 8 INCHES.
ALL FILL IN ROADWAYS AND PARKING AREAS IS TO BE CLASSIFIED TYPE 2 COMPACTED TO 90% DENSITY; COMPACTION TO BE DETERMINED BY ASTM D-1557-66T (MODIFIED PROCTOR). ANY FILL WITHIN THE BUILDING AREA IS TO BE COMPACTED TO A MINIMUM OF OF 95% AS DETERMINED BY METHODS PREVIOUSLY MENTIONED. FILLS FOR POND EMBANKMENTS SHALL BE COMPACTED AS PER THE PROJECT ENGINEER'S SPECIFICATIONS. ALL OTHER FILLS SHALL BE COMPACTED SUFFICIENTLY SO AS TO BE STABLE AND PREVENT EROSION AND SLIPPAGE.

INSTALLATION OF SOD SHOULD FOLLOW THE PERMANENT SEEDING DATES. PERMANENT SOD IS TO BE STATE APPROVED SOD; LIME AND FERTILIZER PER PERMANENT SEEDING SPECIFICATIONS AND LIGHTLY IRRIGATE SOIL PRIOR TO LAYING SOD. SOD IS TO BE LAID ON THE CONTOUR WITH ALL ENDS TIGHTLY ABUTTING. JOINTS ARE TO BE STAGGERED BETWEEN ROWS. WATER AND ROLL OR TAMP SOD TO INSURE POSITIVE ROOT CONTACT WITH THE SOIL. ALL SLOPES STEEPER THAN 3:1, AS SHOWN, ARE TO BE PERMANENTLY SODDED OR PROTECTED WITH APPROVED EROSION CONTROL NETTING. ADDITIONAL WATERING FOR ESTABLISHMENT MAY BE REQUIRED. SOD IS NOT TO BE APPLIED ON FROZEN GROUND. SOD SHALL NOT BE HARVESTED OR TRANSPLANTED WHEN MOISTURE CONTENT (DRY OR WET) AND/OR EXTREME TEMPERATURE MAY ADVERSELY AFFECT ITS SURVIVAL. IN THE ABSENCE OF ADEQUATE RAINFALL, IRRIGATION SHOULD BE PERFORMED TO INSURE ESTABLISHED SOD.

SLOPE STABLIZATION, SEEDING METHOD & MULCHING
SLOPES OR 4:1 OR GREATER (HORIZONTAL: VERTICAL)

SLOPES SHALL BE HYDROSEEDED WITH THE MIXTURES AND RATES INDICATED IN THE PERMANENT SEEDING MIXTURE SCHEDULE. STRAW OR HAY MULCH SHALL BE APPLIED AT A RATE OF 2,000 LBS./ACRE. STRAW OR HAY MULCH SHALL BE ANCHORED WITH BioD—Mesh60 NETTING AS MANUFACTURED BY ROLANKA INTERNATIONAL OR APPROVED EQUIVALENT. NETTING TO BE INSTALLED PER MANUFACTURER SPECIFICATIONS.

GENTLE SLOPE AND FLAT AREAS


AREA SHALL BE SEEDED BY HYDROSEEDING OR BRODCASTING WITH THE MIXTURES AND RATES INDICATED ON THE PERMANENT SEEDING MIXTURE SCHEDULE. HYDROSEEDED AREAS SHALL BE MULCHED WITH A WOOD FIBER MULCH APPLIED AT A RATE OF 500 LBS./ACRE. BROADCAST AREAS SHAL BE MULCHED WITH HAY OR STRAW AT A RATE OF 2,000 LBS./ACRE. AREAS SEEDED BY BROADCASTING SHALL BE LIGHTLY RAKED AND PACED PRIOR TO PLACING


AREAS REMAINING DISTURBED FOR 20 DAYS OR MORE SHALL BE STABLIZED AS FOLLOWS:

SCARIFY SOILS IF COMPACTED, LIME TO pH OF 6.0 IF REQUIRED, FERTILIZE WITH
600 LBS./ACRE. 5-10-10 FERTILIZER IF REQUIRED. SEED WITH SPECIES AND RATE
SHOWN BELOW. MULCH WITH HAY OR STRAW AT A RATE OF 2,000 LBS./ACRE.
ANCHOR MULCH WITH NETTING OF WOOD FIBER OR JUTE IF STEEP SLOPE OR HIGH
POTENTIAL FOR EROSION.

SPECIES
RYEGRASS (ANNUAL OR PERENNIAL)
(USE WINTER RYE IF SEEDING IN
OCT./NOV.)

APPLICATION RATE
30 LBS./ACRE
(0.7 LBS./1,000 SF)








SMALL TEMPORARY SETTLING BASIN

NOT TO SCALE

TEMPORARY WEIR IS USED ACROSS STORM DRAINAGE CHANNELS TO FORM SETTLEMENT BASIN FOR DEWATERING OPERATIONS. ADDITIONAL LOCATIONS AND DESIGNS OF SETTLING BASINS OTHER THAN THOSE SHOWN ON THE PLANS SHALL BE APPROVED BY ENGINEER.








WARNING— IT IS A VIOLATION OF NEW YORK EDUCATIONAL LAW, SECTION 7209.2, FOR ANY PERSON, UNLESS ACTING UNDER THE DIRECTION OF A LICENSED PROFESSIONAL ENGINEER OR LAND SURVEYOR, TO ALTER THIS DOCUMENT IN ANY WAY. IF ALTERED, THE ALTERING PERSON SHALL COMPLY WITH THE REQUIREMENTS OF NEW YORK EDUCATIONAL LAW, SECTION 7209.2

ONLY MAPS WITH EMBOSSED SEALS ARE GENUINE COPIES OF THE ORIGINAL WORK AND OPINION. MAPS NOT BEARING EMBOSSED SEALS SHOULD NOT BE RELIED UPON SINCE OTHER THAN EMBOSSED—SEAL COPIES MAY CONTAIN UNAUTHORIZED

ND UNDETECTABLE MODIFICATIONS, DELETIONS, ADDITIONS


ND CHANGES.



- INSTALLATION NOTES:

  1. AREA CHOSEN FOR STOCKPILING OPERATIONS SHALL BE DRY AND STABLE
- 2. MAXIMUM SLOPE OF STOCKPILES SHALL BE 2:1.
- 3. UPON COMPLETION OF SOIL STOCKPILING EACH PILE SHALL BE SURROUNDED WITH EITHER SILT FENCING OR HAY BALES, THEN STABILIZED WITH VEGETATION OR COVERED.
- 4. SEE SPECIFICATIONS FOR INSTALLATION OF SILT FENCE.

SOIL STOCKPILE DETAI



# CONSTRUCTION NOTES FOR FABRICATED SILT FENCE 1. WOVEN WIRE FENCE TO BE FASTENED SECURELY TO FENCE POST WITH

- WIRE TIES OR STAPLES.

  2. FILTER CLOTH TO BE FASTENED SECURELY TO WOVEN WIRE FENCE WITH
- TIES SPACED EVERY 24" AT TOP AND MID SECTION.

  WHEN TWO SECTIONS OF FILTER CLOTH ADJOIN EACH OTHER THEY SHALL
- BE OVERLAPPED BY 6" AND FOLDED.

  4. MAINTENANCE SHALL BE PERFORMED AS NEEDED AND MATERIAL REMOVED WHEN 'BULGES' DEVELOP IN THE SILT FENCE.
- WHEN BULGES DEVELOP IN THE SILT FENCE.

  SILT FENCE LOCATION SHALL BE STAKED BY A LICENSED LAND SURVEYOR IN THE STATE OF NEW YORK PRIOR TO THE COMMENCEMENT OF CONSTRUCTION.
- THE STATE OF NEW YORK PRIOR TO THE COMMENCEMENT OF CONSTRUCTION.

  POST: STEEL EITHER 'T' OR 'U' TYPE OR 2" HARDWOOD


  FENCE: WOVEN WIRE, 14 1/2 GA. 6" MAX. MESH OPENING

  FILTER CLOTH: FILER X, MIRAFI 100X, STABILINKA T140N OR APPROVED EQUAL

PREFABRICATED UNIT: GEIOFAB, ENVIROFENCE, OR APPROVED EQUAL.

DOUBLE SILT FENCE DETAIL

NOT TO SCALE



# CONSTRUCTION SPECIFICATIONS

- STONE SIZE USE 2" STONE, OR RECLAIMED OR RECYCLED CONCRETE EQUIVALENT.
   LENGTH NOT LESS THAN 50 FEET (EXCEPT ON A SINGLE RESIDENCE LOT WHERE A 30 FOOT MINIMUM LENGTH WOULD APPLY).
- THICKNESS NOT LESS THAN SIX (6) INCHES.
   WIDTH TWELVE (12) FOOT MINIMUM, BUT NOT LESS THAN THE FULL WIDTH AT POINTS WHERE INGRESS OR EGRESS OCCURS. TWENTY-FOUR (24) FOOT IF SINGLE ENTRANCE TO SITE.

5. FILTER CLOTH - WILL BE PLACED OVER THE ENTIRE AREA PRIOR TO PLACING

OF STONE.

6. SURFACE WATER — ALL SURFACE WATER FLOWING OR DIVERTED TOWARD CON—STRUCTION ENTRANCES SHALL BE PIPED ACROSS THE ENTRANCE. IF PIPING IS IMPRACTICAL, A MOUNTABLE BERM WITH 5:1 SLOPES WILL BE PERMITTED.

7. MAINTENANCE - THE ENTRANCE SHALL BE MAINTAINED IN A CONDITION WHICH WILL

PREVENT TRACKING OR FLOWING OF SEDIMENT ONTO PUBLIC RIGHTS-OF-WAY, ALL


SEDIMENT SPILLED, DROPPED, WASHED OR TRACTED ONTO PUBLIC RIGHTS—OF—WAY MUST BE REMOVED IMMEDIATELY.


8. WHEN WASHING IS REQUIRED, IT SHALL BE DONE ON A AREA STABILIZED WITH STONE AND WHICH DRAINS INTO AN APPROVED SEDIMENT TRAPPING DEVICE.

9. PERIODIC INSPECTION AND NEEDED MAINTENANCE SHALL BE PROVIDED AFTER EACH

STABILIZED CONSTRUCTION ENTRANCE
NOT TO SCALE

FOR CONSTRUCTION SPECIFICATIONS REFER TO "NY GUIDELINES FOR URBAN EROSION AND SEDIMENT CONTROL"





SLOPE STABILIZATION DETAIL NOT TO SCALE

1. STABILIZE PREPARED EARTHEN SLOPE WITH A BIODEGRADABLE NATURAL FIBER NETTING APPROVED TYPES ARE AS FOLLOWS:

-C350 -NORTH AMERICAN GREEN #1-800-772-2040
-ECOCOIR 9000- EASTERN PRODUCTS, INC. #1-201-234-5050
-ERO-MAT V125C- EROSION CONTROL TECH. #1-800-245-0551
-ALL SLOPE RESTORATION TO GET 4" TOPSOIL


SEED SLOPE PRIOR TO INSTALLING EROSION CONTROL NETTING.
 AFTER NETTING IS INSTALLED, PLANT GROUND—COVER, TREES & FORSYTHIA THROUGH SLITS CUT IN FABRIC.

BY	DATE	DESCRIPTION
ММ	11/13/23	PER PH & PB COMMENTS
ММ	8/7/23	SITE RE-DESIGN
ММ	2/6/23	PH CONSULTANT COMMENTS
ММ	1/17/23	PUBLIC HEARING COMMENTS
ММ	3/21/22	DEC EMAIL DATED 03/11/22
ММ	12/2/21	PER PB MTG & AF COMMENT LETTER
ММ	9/16/21	PREPARATION OF PRELIMINARY PLANS
ММ	5/19/21	REVISION PER PB MTG. & COMMENT LETTERS
ММ	3/23/21	ROAD LAYOUT REVISION PER PB MTG.
	MM MM MM MM MM MM MM MM	MM 11/13/23 MM 8/7/23 MM 2/6/23 MM 1/17/23 MM 3/21/22 MM 12/2/21 MM 9/16/21 MM 5/19/21

# ARDEN CONSULTING ENGINEERS, PLLC P.O. BOX 340 MONROE, N.Y.

T: 845-782-8114 E: MAM@ARDENCONSULTING.NET

SITE PLAN & LOT LINE COMBINATION FOR DAVIDSON DRIVE HOLDINGS, LLC LAKE STATION ROAD





MM CHECKED:

COPYRIGHT 2021, ARDEN CONSULTING ENGINEERS, P.L.L.C. — ALL RIGHTS RESERVED

TOWN

ICHAEL A. MORGANTE, P.E.





NOT TO SCALE NOTES:

1. THOROUGHLY SOAK THE GROUND COVER ROOT BALL AND ADJACENT PREPARED SOIL SEVERAL TIMES DURING THE FIRST MONTH AFTER PLANTING AND REGULARLY THROUGHOUT THE FOLLOWING TWO SUMMERS. 2. SOIL AMENDMENTS: MODIFY HEAVY CLAY OR SILT SOILS (MORE THAN 40% CLAY OR SILT) BY ADDING COMPOSTED PINE BARK

DECIDUOUS & EVERGREEN SHRUB PLANTING DETAIL

(UP TO 30% BY VOLUME) OR GYPSUM MODIFY EXTREMELY SANDY SOILS (MORE THAN 85% SAND) BY ADDING ORGANIC MATTER AND/OR DRY, SHREDDED CLAY LOAM UP TO 30% OF THE TOTAL MIX. 3. ALL GROUND COVER AREAS SHALL BE TREATED WITH A PRE-EMERGENT PER MANUFACTURER'S SPECIFICATIONS

AVOID PURCHASING TREES WITH TWO LEADERS DO NOT STAKE OR WRAP TRUNK-HOLE SHALL BE 2 1/2 TIMES\_ THE WIDTH OF THE ROOT BALL 3" DOUBLE SHREDDED HARDWOOD MULCH (DO NOT PLACE MULCH IN CONTACT WITH TREE TRUNK) ROPES AT TOP OF BALL SHALL BE\_ CUT AND REMOVED. FOLD BACK TOP 1/3 OF BURLAP. ALL NON-BIODEGRADABLE MATERIAL SHALL BE REMOVED. UNDISTURBED SUBGRADE-

DIG WIDE, SHALLOW HOLE WITH-

TAPERED SIDES

OR REMOVE ONE AT PLANTING: OTHERWISE, DO NOT PRUNE TREE AT PLANTING EXCEPT FOR SPECIFIC STRUCTURAL CORRECTIONS SET ROOT BALL FLUSH TO GRADE OR SEVERAL INCHES HIGHER IN POORLY DRAINING SOILS CUT BANDS OF WIRE BASKET AND FOLD AWAY FROM TOP OF ROOT BALL ~4" BUILT-UP EARTH SAUCER BACKFILL SOIL ✓¹1 PART SOIL AMENDMENT (BASED ON SOIL TEST) 3 PARTS NATIVE TOPSOIL 4-6" DEEPER THAN ROOT BALL TAMP SOIL SOLIDLY AROUND BASE OF ROOT BALL SET ROOT BALL ON FIRM PAD IN


BOTTOM OF HOLE

<u>DECIDUOUS TREE PLANTING DETAIL</u> NOT TO SCALE

. FOR CONTAINER-GROWN TREES, USE FINGERS OR SMALL HAND TOOLS TO PULL THE ROOTS OUT OF THE OUTER LAYER OF POTTING SOIL; THEN CUT OR PULL APART ANY ROOTS CIRCLING

THE PERIMETER OF THE CONTAINER 2. THOROUGHLY SOAK THE TREE ROOT BALL AND ADJACENT PREPARED SOIL SEVERAL TIMES DURING THE FIRST MONTH AFTER PLANTING AND REGULARLY THROUGHOUT THE FOLLOWING TWO

SOIL AMENDMENTS: \*MODIFY HEAVY CLAY OR SILT SOILS (MORE THAN 40% CLAY OR SILT) BY ADDING COMPOSTED PINE BARK (UP TO 30% BY VOLUME) OR GYPSUM "MODIFY EXTREMELY SANDY SOILS (MORE THAN 85% SAND) BY ADDING ORGANIC MATTER AND/OR DRY, SHREDDED CLAY LOAM UP TO 30% OF THE TOTAL MIX



EVERGREEN TREE PLANTING DETAIL NOT TO SCALE

AND/OR DRY, SHREDDED CLAY LOAM UP TO 30% OF THE TOTAL MIX

FOR CONTAINER-GROWN TREES, USE FINGERS OR SMALL HAND TOOLS TO PULL THE ROOTS OUT OF THE OUTER LAYER OF POTTING SOIL; THEN CUT OR PULL APART ANY ROOTS CIRCLING THE PERIMETER OF THE 2. THOROUGHLY SOAK THE TREE ROOT BALL AND ADJACENT PREPARED SOIL SEVERAL TIMES DURING THE FIRST MONTH AFTER PLANTING AND REGULARLY THROUGHOUT THE FOLLOWING TWO SUMMERS.

"MODIFY HEAVY CLAY OR SILT SOILS (MORE THAN 40% CLAY OR SILT) BY ADDING COMPOSTED PINE BARK (UP TO 30% BY VOLUME) OR GYPSUM "MODIFY EXTREMELY SANDY SOILS (MORE THAN 85% SAND) BY ADDING ORGANIC MATTER

<u>ERNST SEED CO. NATIVE DETENTION AREA SEEDING SPECIFICATIONS (ERNMX—183):</u> SWITCHGRASS, 'SHAWNEE' (PANICUM VIRGATUM, 'SHAWNEE') REDTOP PANICGRASS, COASTAL PLAIN NC ECOTYPE (PANICUM RIGIDULUM (P. STIPITATUM), COASTAL PLAIN NC ECOTYPE) VIRGINIA WILDRYE, PA ECOTYPE (ELYMUS VIRGINICUS, PA ECOTYPE) GREEN BULRUSH, PA ECOTYPE (SCIRPUS ATROVIRENS, PA ECOTYPE) AUTUMN BENTGRASS, PA ECOTYPE (AGROSTIS PERENNANS, PA ECOTYPE) PATH RUSH, PA

1. SOW ABOVE MIX AT A RATE OF 20 LBS./ACRE OR 1/2 LB PER 1,000 S.F. . SUPPLEMENT ABOVE MIX WITH A COVER CROP OF GRAIN RYE AT 30 LBS/ACRE. 3. MOW SEEDED AREA ONCE PER YEAR IN LATE SPRING.

ECOTYPE (JUNCUS TENUIS, PA ECOTYPE)

THE ROLE OF PLANTS IN ALL STORM WATER MANAGEMENT FACILITIES IS TO PREVENT EROSION AND SLOW WATER MOVEMENT, HOLD OR CONVERT POLLUTANTS, ENHANCE INFILTRATION AND EVAPOTRANSPIRATION, AND ENCOURAGE WILDLIFE. THE DESIGNER CAN SELECT PLANT SPECIES OR MIXES THAT MEET THE CRITICAL OBJECTIVES AND EXTREME CONDITIONS UNDER WHICH PLANTS MUST SURVIVE. NATIVE GRASSES ESTABLISH RAPIDLY, WITH FIBROUS ROOT SYSTEMS THAT TOLERATE FAST-MOVING WATER. HERBACEOUS SPECIES PLAY THE ROLE OF ADDING AESTHETICS, TEXTURE, AND PROVIDING WILDLIFE FOOD AND HABITAT. WOODY SPECIES ASSIST IN EVAPOTRANSPIRATION, WHILE PREVENTING EROSION.

IN ADDITION TO STRUCTURAL MAINTENANCE, SILTATION NEEDS TO BE REMOVED AS NEEDED. PLANTS NEED TO BE TRIMMED BACK TO MAINTAIN AESTHETIC VALUE AND INVASIVE SPECIES NEED TO BE CONTROLLED. CLOSE MOWING OR EXTENSIVE CHEMICAL USE IS NOT CONDUCIVE TO WATER QUALITY IMPROVEMENT AND

SITE PREPARATION INVASIVE SPECIES, PARTICULARLY THOSE THAT WILL ADAPT TO WET CONDITIONS SHOULD BE REMOVED OR SPRAYED BEFORE THEY BECOME INCORPORATED INTO HE SITE. NORMAL VEGETATION CAN BE WORKED INTO THE TOPSOIL, WHICH SHOULD BE STOCKPILED UNTIL THE FINAL GRADE HAS BEEN ESTABLISHED. WITH THE ENGINEER'S SPECIFICATIONS AND DIMENSIONS IN HAND, ON-SITE CONSTRUCTION OF THE BERM AND OUTLETS MUST BE EXECUTED CAREFULLY IN ORDER TO MAINTAIN STRUCTURAL INTEGRITY. THE INFILTRATION AND PLAN GROWTH AREAS SHOULD BE LOOSE AND FRIABLE, HIGH IN ORGANIC MATTER, AND COMPLETED WITHOUT COMPACTIONS FROM HEAVY EQUIPMENT. BY USING THE "DIG AND DROP" METHOD, ONE CAN USE AN EXCAVATOR TO DIG AND DROP EACH AREA OF THE BOTTOM SOIL IN A LOOSE MANNER. AT THIS POINT, ONE CAN INCORPORATE LIME, COMPOSTED LEAVES, AND/OR GRASS CLIPPINGS. THE EXCAVATION MACHINE DOES NOT MOVE OVER THE FINISHED SURFACE, THUS AVOIDING UNNECESSARY COMPACTION. NATIVE VEGETATION CAN BE PLANTED OR SEEDED OVER THIS UNEVEN, ABSORBENT SURFACE. SEEDING AND PLANTING METHODS

SEEDING AND PLANTING SHOULD BEGIN IMMEDIATELY UPON COMPLETION OF THE STRUCTURE WHEN THE SOIL IS STILL FRIABLE AND BEFORE INVASIVE WEEDS ALLOW THE BASIN TO DRAIN TO A FEW INCHES BEFORE SEEDING. BROADCAST SEED EVENLY OVER EACH UNIT BY HAND SEEDING OR HYDROSEEDING. SEEDING RATES ARE GENERALLY LOW (1/2 LB PER 1,000 SQ FT). THE USE OF A SEED FILLER; I.E., PAM-12, CAN BE USED TO CREATE A MIX OF 10 LB PER 1,000 SQ FT (I.E., 9-1/2 LB OF PAM-12 MIXED WITH 1/2 LB OF SEED), WHICH CAN BE BROADCAST EVENLY OVER THE AREA. BARLEY, OATS, OR RYE CAN PROVIDE TEMPORARY VEGETATION TO PROTECT THE SOIL IN STORM WATER MANAGEMENT FACILITIES UNTIL PERMANENT VEGETATION CAN BE ESTABLISHED. THE USE OF NATIVE SPECIES; I.E., VIRGINIA WILD RYE, CAN CREATE AN INTERMEDIATE VEGETATIVE COVER THAT SUCCEEDS TO NATIVE LONG-TERM VEGETATION. STRAW MULCH OR STRAW COCONUT MATS ARE FREQUENTLY USED TO CONTROL EROSION AND PROTECT EMERGING SEEDLINGS FROM EXTREME TEMPERATURES AND DRYING OUT. MULCH SHOULD BE SPARSE TO ALLOW SUNLIGHT TO REACH THE GROUND. TRANSPLANTED SEEDLINGS AND SHRUBS NEED TEMPORARY WATER UNTIL THEY BECOME WELL ROOTED. IRRIGATION OF SEEDED AREAS IS OF VALUE UNTIL SEEDLINGS BECOME ESTABLISHED.

NORTHEAST PREMIUM WILDFLOWER SEED MIXTURE SEEDLAND PRODUCT CODE: WFAR-0605 [OR EQUAL]

PLANTING RATE: 5-10 LBS./ACRE OR 4 OZ./1000 SQ. FT. (1/2 ACRE OR LESS) USE DOUBLE RATE IF HYDRO-SEEDING

**GENERAL LANDSCAPING NOTES:** REVISED 2/18/2015 PLANT QUALITY AND HANDLING NOTES: REVISED 2/18/2015

1. ALL PLANT MATERIAL SHALL CONFORM TO THE AMERICAN STANDARD FOR NURSERY STOCK (ANSI Z60.1—2004) OR LATEST REVISION AS PUBLISHED BY THE AMERICAN NURSERY AND LANDSCAPE ASSOCIATION.
2. IN ALL CASES, BOTANICAL NAMES LISTED WITHIN THE APPROVED OR FINAL PLANT LIST SHALL TAKE PRECEDENCE OVER COMMON NAMES.
3. ALL PLANTS SHALL BE OF SELECTED SPECIMEN QUALITY, EXCEPTIONALLY HEAVY, TIGHTLY KNIT, SO TRAINED OR FAVORED IN THEIR DEVELOPMENT AND APPEARANCE AS TO BE SUPERIOR IN FORM, NUMBER OF BRANCHES, COMPACTNESS AND SYMMETRY. ALL PLANTS SHALL HAVE A NORMAL HABIT OR SOUND, HEALTHY, VIGOROUS PLANTS WITH WELL DEVELOPED ROOT SYSTEM. PLANTS SHALL BE FREE OF DISEASE, INSECT PESTS, EGGS OR LARVAE. 4. PLANTS SHALL NOT BE PRUNED BEFORE DELIVERY. TREES WITH ABRASION OF THE BARK, SUNSCALDS, DISFIGURING KNOTS OR FRESH CUTS OF LIMBS OVER ONE AND ONE-FOURTH INCHES (1-1/4") WHICH 5. ALL PLANTS SHALL BE TYPICAL OF THEIR SPECIES OR VARIETY AND SHALL HAVE A NORMAL HABIT OF GROWTH AND BE LEGIBLY TAGGED WITH THE PROPER NAME AND SIZE

5. THE ROOT SYSTEM OF EACH PLANT SHALL BE WELL PROVIDED WITH FIBROUS ROOTS. ALL PARTS SHALL BE SOUND, HEALTHY, VIGOROUS, WELL—BRANCHED AND DENSELY FOLIATED WHEN IN LEAF.

'. ALL PLANTS DESIGNATED BALL AND BURLAP (B&B) MUST BE MOVED WITH THE ROOT SYSTEM AS SOLID UNITS WITH BALLS OF EARTH FIRMLY WRAPPED WITH BURLAP. THE DIAMETER AND DEPTH OF THE BALLS OF EARTH MUST BE SUFFICIENT TO ENCOMPASS THE FIBROUS ROOT FEEDING SYSTEMS NECESSARY FOR THE HEALTHY DEVELOPMENT OF THE PLANT. NO PLANT SHALL BE ACCEPTED WHEN THE BALL OF EARTH SURROUNDING ITS ROOTS HAS BEEN BADLY CRACKED OR BROKEN PREPARATORY TO OR DURING THE PROCESS OF PLANTING. THE BALLS SHALL REMAIN INTACT DURING ALL OPERATIONS. ALL PLANTS HAT CANNOT BE PLANTED AT ONCE MUST BE HEELED-IN BY SETTING IN THE GROUND AND COVERING THE BALLS WITH SOIL OR MULCH AND THEN WATERING. HEMP BURLAP AND TWINE IS PREFERABLE TO TREATED. IF TREATED BURLAP IS USED, ALL TWINE IS TO BE CUT FROM AROUND THE TRUNK AND ALL BURLAP IS TO BE REMOVED. 8. PLANTS TRANSPORTED TO THE PROJECT IN OPEN VEHICLES SHALL BE COVERED WITH TARPS OR OTHER SUITABLE COVERS SECURELY FASTENED TO THE BODY OF THE VEHICLE TO PREVENT INJURY TO THE PLANTS. CLOSED VEHICLES SHALL BE ADEQUATELY VENTILATED TO PREVENT OVERHEATING OF THE PLANTS. EVIDENCE OF INADEQUATE PROTECTION FOLLOWING DIGGING, CARELESSNESS WHILE IN TRANSIT, OR IMPROPER HANDLING OR STORAGE SHALL BE CAUSE FOR REJECTION OF PLANT MATERIAL. ALL PLANTS SHALL BE KEPT MOIST, FRESH, AND PROTECTED. SUCH PROTECTION SHALL ENCOMPASS THE ENTIRE PERIOD DURING WHICH THE PLANTS ARE IN TRANSIT, BEING HANDLED, OR ARE IN TEMPORARY STORAGE. 9. ALL PLANT MATERIAL SHALL BE INSTALLED IN ACCORDANCE WITH THE CORRESPONDING LANDSCAPE PLAN AND PLANTING DETAILS.

O. LANDSCAPE CONTRACTOR SHALL MAKE BEST EFFORT TO INSTALL PLANTINGS ON THE SAME DAY AS DELIVERY. IF PLANTS ARE NOT PLANTED IMMEDIATELY ON SITE, PROPER CARE SHALL BE TAKEN TO PLACE
THE PLANTINGS IN PARTIAL SHADE WHEN POSSIBLE. THE ROOT BALL SHALL BE KEPT MOIST AT ALL TIME AND COVERED WITH MOISTENED MULCH OR AGED WOODCHIPS. PROPER IRRIGATION SHALL BE SUPPLIED
SO AS TO NOT ALLOW THE ROOT BALL TO DRY OUT. PLANTINGS SHALL BE UNTIED AND PROPER SPACING SHALL BE ALLOTTED FOR AIR CIRCULATION AND TO PREVENT DISEASE, WILTING, AND LEAF LOSS. PLANTS THAT REMAIN UNPLANTED FOR A PERIOD OF TIME GREATER THAN THREE (3) DAYS SHALL BE HEALED IN WITH TOPSOIL OR MULCH AND WATERED AS REQUIRED TO PRESERVE ROOT MOISTURE. 1. NO PLANT MATERIAL SHALL BE PLANTED IN MUDDY OR FROZEN SOIL.

2. PLANTS WITH INJURED ROOTS OR BRANCHES SHALL BE PRUNED PRIOR TO PLANTING UTILIZING CLEAN, SHARP TOOLS. ONLY DISEASED OR INJURED PLANTS SHALL BE REMOVED.

3. IF ROCK OR OTHER UNDERGROUND OBSTRUCTION IS ENCOUNTERED, THE LANDSCAPE DESIGNER RESERVES THE RIGHT TO RELOCATE OR ENLARGE PLANTING PITS OR DELETE PLANT MATERIAL FROM THE 14. IF PLANTS ARE PROPOSED WITHIN SIGHT TRIANGLES, TREES SHALL BE LIMBED AND MAINTAINED TO A HEIGHT OF SEVEN FEET (7') ABOVE GRADE, AND SHRUBS, GROUND COVER, PERENNIALS, AND ANNUALS SHALL BE MAINTAINED TO A HEIGHT NOT TO EXCEED TWO FEET (2') ABOVE GRADE UNLESS OTHERWISE NOTED OR SPECIFIED BY THE GOVERNING MUNICIPALITY OR AGENCY. 15. INSTALLATION SHALL OCCUR DURING THE FOLLOWING SEASONS:

PLANTS (MARCH 15 - DECEMBER 15) LAWNS (MARCH 15 - JUNE 15 OR SEPTEMBER 1 - DECEMBER 1) 16. THE FOLLOWING TREES ARE SUSCEPTIBLE TO TRANSPLANT SHOCK AND SHALL NOT BE PLANTED DURING THE FALL SEASON (STARTING SEPTEMBER 15):

ABIES CONCOLOR CORNUS VARIETIES OSTRYA VIRGINIANA ACER BUERGERIANUM CRATAEGUS VARIETIES PINUS NIGRA CUPRESSOCYPARIS LEYLANDII PLATANUS VARIETIES ACER FREEMANII ACER RUBRUM FAGUS VARIETIES POPULUS VARIETIE ACER SACCHARINUM HALESIA VARIETIES PRUNUS VARIETIES BETULA VARIETIES ILEX X FOSTERII CARPINUS VARIETIES ILEX NELLIE STEVENS QUERCUS VARIETIES (NOT Q. PALUSTRIS) CEDRUS DEODARA ILEX OPACA SALIX WEEPING VARIETIES

CELTIS VARIETIES JUNIPERUS VIRGINIANA SORBUS VARIETIES CERCIDIPHYLLUM VARIETIES KOELREUTERIA PANICULATA TAXODIUM VARIETIES CERCIS CANADENSIS LIQUIDAMBAR VARIETIES TAXUX B REPANDENS LIRIODENDRON VARIETIES ULMUS PARVIFOLIA VARIETIES

NYSSA SYLVATICA ZELKOVA VARIETIES 17. IF A PROPOSED PLANT IS UNATTAINABLE OR ON THE FALL DIGGING HAZARD LIST, AN EQUIVALENT SPECIES OF THE SAME SIZE MAY BE REQUESTED FOR SUBSTITUTION OF THE ORIGINAL PLANT. ALL SUBSTITUTIONS SHALL BE APPROVED BY THE PROJECT LANDSCAPE DESIGNER OR MUNICIPAL OFFICIAL PRIOR TO ORDERING AND INSTALLATION. 18. DURING THE COURSE OF CONSTRUCTION/PLANT INSTALLATION, EXCESS AND WASTE MATERIALS SHALL BE CONTINUOUSLY AND PROMPTLY REMOVED AT THE END OF EACH WORK DAY. ALL DEBRIS, MATERIALS, AND TOOLS SHALL BE PROPERLY STORED, STOCKPILED OR DISPOSED OF AND ALL PAVED AREAS SHALL BE CLEANED. 19. THE LANDSCAPE CONTRACTOR SHALL DISPOSE OF ALL RUBBISH AND EXCESS SOIL AT HIS EXPENSE TO AN OFF-SITE LOCATION AS APPROVED BY THE LOCAL MUNICIPALITY. 20. A 90-DAY MAINTENANCE PERIOD SHALL BEGIN IMMEDIATELY AFTER ALL PLANTS HAVE BEEN SATISFACTORILY INSTALLED.

1. MAINTENANCE SHALL INCLUDE, BUT NOT BE LIMITED TO, REPLACING MULCH THAT HAS BEEN DISPLACED BY EROSION OR OTHER MEANS, REPAIRING AND RESHAPING WATER RINGS OR SAUCERS, MAINTAINING STAKES AND GUYS IF ORIGINALLY REQUIRED, WATERING WHEN NEEDED OR DIRECTED, WEEDING, PRUNING, SPRAYING, FERTILIZING, MOWING THE LAWN, AND PERFORMING ANY OTHER WORK REQUIRED TO KEEP THE PLANTS IN A HEALTHY CONDITION. 22. MOW ALL GRASS AREAS AT REGULAR INTERVALS TO KEEP THE GRASS HEIGHT FROM EXCEEDING THREE INCHES (3"). MOWING SHALL BE PERFORMED ONLY WHEN GRASS IS DRY. MOWER BLADE SHALL BE SET TO REMOVE NO MORE THAN ONE THIRD (1/3) OF THE GRASS LENGTH. WHEN THE AMOUNT OF GRASS IS HEAVY, IT SHALL BE REMOVED TO PREVENT DESTRUCTION OF THE UNDERLYING TURF. MOW GRASS AREAS IN SUCH A MANNER AS TO PREVENT CLIPPINGS FROM BLOWING ON PAVED AREAS, AND SIDEWALKS. CLEANUP AFTER MOWING SHALL INCLUDE SWEEPING OR BLOWING OF PAVED AREAS AND SIDEWALKS TO CLEAR THEM FROM MOWING DEBRIS. 23. GRASSED AREAS DAMAGED DURING THE PROCESS OF THE WORK SHALL BE THE RESPONSIBILITY OF THE CONTRACTOR, WHO SHALL RESTORE THE DISTURBED AREAS TO A CONDITION SATISFACTORY TO THE PROJECT LANDSCAPE DESIGNER, MUNICIPAL OFFICIAL, OR OWNER/OWNER'S REPRESENTATIVE. THIS MAY INCLUDE FILLING TO GRADE, FERTILIZING, SEEDING, AND MULCHING. 24. SHOULD THE OWNER REQUIRE MAINTENANCE BEYOND THE STANDARD 90-DAY MAINTENANCE PERIOD, A SEPARATE CONTRACT SHALL BE ESTABLISHED. 25. LANDSCAPE CONTRACTOR SHALL WATER NEW PLANTINGS FROM TIME OF INSTALL AND THROUGHOUT REQUIRED 90-DAY MAINTENANCE PERIOD UNTIL PLANTS ARE ESTABLISHED. IF ON-SITE WATER IS NOT AVAILABLE AT THE PROJECT LOCATION, THE LANDSCAPE CONTRACTOR SHALL FURNISH IT BY MEANS OR A WATERING TRUCK OR OTHER ACCEPTABLE MANNER. 26. THE QUANTITY OF WATER APPLIED AT ONE TIME SHALL BE SUFFICIENT TO PENETRATE THE SOIL TO A MINIMUM OF EIGHT INCHES (8") IN SHRUB BEDS AND SIX INCHES (6") IN TURF AREAS AT A RATE WHICH WILL PREVENT SATURATION OF THE SOIL 27. IF AN AUTOMATIC IRRIGATION SYSTEM HAS BEEN INSTALLED, IT CAN BE USED FOR WATERING PLANT MATERIAL. HOWEVER, FAILURE OF THE SYSTEM DOES NOT ELIMINATE THE LANDSCAPE CONTRACTOR'S RESPONSIBILITY OF PLANT HEALTH AND ESTABLISHMENT.

LAWN (SEED OR SOD) NOTES: . SEED MIXTURE SHALL BE FRESH, CLEAN, NEW CROP SEED. SOD SHALL BE STRONGLY ROOTED, UNIFORM IN THICKNESS, AND FREE OF WEEDS, DISEASE, AND PESTS SEED OR SOD SHALL BE PURCHASED FROM A RECOGNIZED DISTRIBUTOR AND SHALL BE COMPOSED OF THE MIX OR BLEND WITHIN THE PROVIDED "SEED SPECIFICATION" OR "SOD SPECIFICATION." REFERENCE LANDSCAPE PLAN FOR AREAS TO BE SEEDED OR LAID WITH SOD. . SEEDING SHALL NOT BE PERFORMED IN WINDY WEATHER. IF THE SEASON OF THE PROJECT COMPLETION PROHIBITS PERMANENT STABILIZATION, TEMPORARY STABILIZATION SHALL BE PROVIDED IN 5. PROTECT NEW LAWN AREAS AGAINST TRESPASSING WHILE THE SEED IS GERMINATING. FURNISH AND INSTALL FENCES, SIGNS, BARRIERS OR ANY OTHER NECESSARY TEMPORARY PROTECTIVE DEVICES. DAMAGE RESULTING FROM TRESPASS, EROSION, WASHOUT, SETTLEMENT OR OTHER CAUSES SHALL BE REPAIRED BY THE LANDSCAPE CONTRACTOR AT HIS EXPENSE. REMOVE ALL FENCES, SIGNS, BARRIERS OR OTHER TEMPORARY PROTECTIVE DEVICES ONCE LAWN HAS BEEN ESTABLISHED.

1. THE LANDSCAPE CONTRACTOR SHALL FURNISH ALL MATERIALS AND PERFORM ALL WORK IN ACCORDANCE WITH THESE SPECIFICATIONS, APPROVED OR FINAL DRAWINGS, AND INSTRUCTIONS PROVIDED BY THE PROJECT LANDSCAPE DESIGNER, MUNICIPAL OFFICIALS, OR OWNER/OWNER'S REPRESENTATIVE. ALL WORK COMPLETED AND MATERIALS FURNISHED AND INSTALLED SHALL BE IN STRICT ACCORDANCE WITH THE INTENTION OF THE SPECIFICATIONS, AND INSTRUCTIONS AND EXECUTED WITH THE STANDARD LEVEL OF CARE FOR THE LANDSCAPE INDUSTRY.

2. WORK MUST BE CARRIED OUT ONLY DURING WEATHER CONDITIONS FAVORABLE TO LANDSCAPE CONSTRUCTION AND TO THE HEALTH AND WELFARE OF PLANTS. THE SUITABILITY OF SUCH WEATHER CONDITIONS SHALL BE DETERMINED BY THE PROJECT LANDSCAPE DESIGNER OR GOVERNING MUNICIPAL OFFICIAL. . IT IS THE RESPONSIBILITY OF THE LANDSCAPE CONTRACTOR, BEFORE ORDERING OR PURCHASING MATERIALS, TO PROVIDE SAMPLES OF THOSE MATERIALS TO THE PROJECT LANDSCAPE DESIGNER OR GOVERNING MUNICIPAL OFFICIAL FOR APPROVAL, IF SO REQUESTED.

4. IF SAMPLES ARE REQUESTED, THE LANDSCAPE CONTRACTOR IS TO SUBMIT CERTIFICATION TAGS FROM TREES, SHRUBS AND SEED VERIFYING TYPE AND PURITY. 5. UNLESS OTHERWISE AUTHORIZED BY THE PROJECT LANDSCAPE DESIGNER OR GOVERNING MUNICIPAL OFFICIAL, THE LANDSCAPE CONTRACTOR SHALL PROVIDE NOTICE AT LEAST FORTY—EIGHT HOURS (48 HRS.) IN ADVANCE OF THE ANTICIPATED DELIVERY DATE OF ANY PLANT MATERIALS TO THE PROJECT SITE. A LEGIBLE COPY OF THE INVOICE, SHOWING VARIETIES AND SIZES OF MATERIALS INCLUDED FOR EACH SHIPMENT SHALL BE FURNISHED TO THE PROJECT LANDSCAPE DESIGNER, OR GOVERNING MUNICIPAL OFFICIAL.
6. THE PROJECT LANDSCAPE DESIGNER OR GOVERNING MUNICIPAL OFFICIAL RESERVES THE RIGHT TO INSPECT AND REJECT PLANTS AT ANY PLACE. 7. EXCESS SNOW THAT CANNOT BE ACCOMMODATED WITHIN THE SNOW DUMP AREAS MUST BE REMOVED FROM THE SITE.

1. LANDSCAPE CONTRACTOR SHALL OBTAIN A SOIL TEST OF THE IN-SITU TOPSOIL BY A CERTIFIED SOIL LABORATORY PRIOR TO PLANTING. LANDSCAPE CONTRACTOR SHALL ALLOW FOR A TWO WEEK TURNAROUND TIME FROM SUBMITTAL OF SAMPLE TO NOTIFICATION OF RESULTS. 2. BASED ON SOIL TEST RESULTS, ADJUST THE RATES OF LIME AND FERTILIZER THAT SHALL BE MIXED INTO THE TOP SIX INCHES (6") OF TOPSOIL. THE LIME AND FERTILIZER RATES PROVIDED WITHIN THE "SEED SPECIFICATION" OR "SOD SPECIFICATION" IS APPROXIMATE AND FOR BIDDING PURPOSES ONLY. IF ADDITIONAL AMENDMENTS ARE NECESSARY, ADJUST THE TOPSOIL AS FOLLOWS: . MODIFY HEAVY CLAY OR SILT SOILS (MORE THAN 40% CLAY OR SILT) BY ADDING COMPOSTED PINE BARK (UP TO 30% BY VOLUME) OR GYPSUM.

 MODIFY EXTREMELY SANDY SOILS (MORE THAN 85%) BY ADDING ORGANIC MATTER AND/OR DRY, SHREDDED CLAY LOAM UP TO 30% OF THE TOTAL MIX. 3. TOPSOIL SHALL BE FERTILE, FRIABLE, NATURAL TOPSOIL OF LOAMING CHARACTER, WITHOUT ADMIXTURE OF SUBSOIL MATERIAL OBTAINED ARABLE SITE, FREE FROM ALL CLAY, LUMPS, COARSE SANDS, STONES, PLANTS, ROOTS, STICKS, AND OTHER FOREIGN MATERIAL GREATER THAN ONE INCH (1□). . TOPSOIL SHALL HAVE A PH RANGE OF 5.0-7.0 AND SHALL NOT CONTAIN LESS THAN 6% ORGANIC MATTER BY WEIGHT

5. OBTAIN TOPSOIL ONLY FROM LOCAL SOURCES OR FROM AREAS HAVING SIMILAR SOIL CHARACTERISTICS TO THAT FOUND AT THE PROJECT SITE. 6. CONTRACTOR SHALL PROVIDE A SIX INCH (6") DEEP LAYER OF TOPSOIL IN ALL PLANTING AREAS. TOPSOIL SHALL BE SPREAD OVER A PREPARED SURFACE IN A UNIFORM LAYER TO ACHIEVE THE DESIRED COMPACTED THICKNESS. THE SPREADING OF TOPSOIL SHALL NOT BE CONDUCTED UNDER MUDDY OR FROZEN SOIL CONDITIONS. . UNLESS OTHERWISE NOTED IN THE CONTRÀCT, THE LANDSCAPE CONTRACTOR SHALL BE RESPONSIBLE FOR THE INSTALLATION OF TOPSOIL AND THE ESTABLISHMENT OF FINE—GRADING WITHIN THE DISTURBED AREA OF THE SITE. 8. LANDSCAPE CONTRACTOR SHALL VERIFY THAT THE SUB-GRADE ELEVATION MEETS THE FINISHED GRADE ELEVATION (LESS THE REQUIRED TOPSOIL), IN ACCORDANCE WITH THE APPROVED OR FINAL GRADING PLAN. . ALL LAWN AND PLANTING AREAS SHALL BE GRADED TO A SMOOTH, EVEN AND UNIFORM PLANE WITH NO ABRUPT CHANGE OF SURFACE AS DEPICTED WITHIN THE APPROVED OR FINAL CONSTRUCTION SET UNLESS OTHERWISE DIRECTED BY THE PROJECT LANDSCAPE DESIGNER OR MUNICIPAL OFFICIAL

O. THE CONTRACTOR SHALL BE RESPONSIBLE FOR PROPER SURFACE AND SUBSURFACE PLANT BED DRAINAGE CONDITIONS EXIST, CORRECTIVE ACTION SHALL BE TAKEN PRIOR TO INSTALLATION. ALL PLANTING AND LAWN AREAS SHALL BE GRADED AND MAINTAINED TO 11. DOUBLE SHREDDED HARDWOOD MULCH OR APPROVED EQUAL SHALL BE USED AS A THREE INCH (3") TOP DRESSING IN ALL SHRUB PLANTING BEDS AND AROUND ALL TREES PLANTED BY LANDSCAPE CONTRACTOR. GROUND COVER, PERENNIAL, AND ANNUAL PLANTING BEDS SHALL BE MULCHED WITH A TWO INCH (2) TOP DRESSING. SINGLE TREES OR SHRUBS SHALL BE MULCHED TO AVOID CONTACT WITH TRUNK OR PLANT STEM. MULCH SHALL BE OF SUFFICIENT CHARACTER AS NOT TO BE EASILY DISPLACED BY WIND OR WATER RUNOFF. . WHENEVER POSSIBLE, THE SOIL PREPARATION AREA SHALL BE CONNECTED FROM PLANTING TO PLANTING. . SOIL SHALL BE LOOSENED WITH A BACKHOE OR OTHER LARGE COARSE—TILING EQUIPMENT UNLESS THE SOIL IS FROZEN OR EXCESSIVELY WET. TILING THAT RESULTS IN FINE GRAINS UNIFORM IN TEXTURE. AFTER THE AREA IS LOOSENED IT SHALL NOT 14. APPLY PRE-EMERGENT WEED CONTROL TO ALL PLANT BEDS PRIOR TO MULCHING. ENSURE COMPATIBILITY BETWEEN PRODUCT AND PLANT MATERIAL.
15. ALL PLANTING SOIL SHALL BE AMENDED WITH THE FOLLOWING:


MYCRO→ TREE SAVER - A DRY GRANULAR MYCORRHIZAL FUNGI INOCULANT THAT IS MIXED IN THE BACKFILL WHEN PLANTING TREES AND SHRUBS. IT CONTAINS SPORES OF BOTH ECTOMYCORRHIZAL FUNGI (VAM), BENEFICIAL RHIZOSPHERE BACTERIA, TERRA-SORB SUPERABSORBENT HYDROGEL TO REDUCE WATER LEACHING, AND SELECTED ORGANIC MICROBIAL NUTRIENTS. • DIRECTIONS FOR USE: USE 3-OZ PER EACH FOOT DIAMETER OF THE ROOT BALL, OR 3-OZ PER INCH CALIPER. MIX INTO THE BACKFILL WHEN TRANSPLANTING TREES AND SHRUBS. MIX PRODUCT IN A RING-SHAPED VOLUME OF SOIL AROUND THE UPPER PORTION OF THE ROOT BALL, EXTENDING FROM THE SOIL SURFACE TO A DEPTH OF ABOUT 8 INCHES, AND EXTENDING OUT FROM THE ROOT BALL ABOUT 8 INCHES INTO THE BACKFILL. APPLY WATER TO SOIL SATURATION. MYCOR→ TREE SAVER→ IS EFFECTIVE FOR ALL TREE AND SHRUB SPECIES EXCEPT RHODODENDRONS, AZALEAS, AND MOUNTAIN LAUREL, WHICH REQUIRE ERICOID MYCORRHIZAE. • SOIL PH: THE FUNGI IN THIS PRODUCT WERE CHOSEN BASED ON THEIR ABILITY TO SURVIVE AND COLONIZE PLANT ROOTS IN A PH RANGE OF 3 TO 9.

• FUNGICIDES: THE USE OF CERTAIN FUNGICIDES CAN HAVE A DETRIMENTAL EFFECT ON THE INOCULATION PROGRAM. SOIL APPLICATION OF ANY FUNGICIDE IS NOT RECOMMENDED FOR TWO WEEKS AFTER APPLICATION. • OTHER PESTICIDES: HERBICIDES AND INSECTICIDES DO NOT NORMALLY INTERFERE WITH MYCORRHIZAL FUNGAL DEVELOPMENT, BUT MAY INHIBIT THE GROWTH OF SOME TREE AND SHRUB SPECIES IF NOT USED PROPERLY.


• FERTILIZER TABLETS ARE PLACED IN THE UPPER 4 INCHES OF BACKFILL SOIL WHEN PLANTING TREES AND SHRUBS.

• TABLETS ARE FORMULATED FOR LONG-TERM RELEASE BY SLOW BIODEGRADATION, AND LAST UP TO 2 YEARS AFTER PLANTING. TABLETS CONTAIN 12-8-8 NPK FERTILIZER, AS WELL AS A MINIMUM OF SEVEN PERCENT (7%) HUMIC ACID BY WEIGHT, MICROBIAL NUTRIENTS DERIVED FROM SEA KELP, PROTEIN BYPRODUCTS, AND YUCCA SCHIDIGERA, AND A COMPLEMENT OF BENEFICIAL RHIZOSPHERE BACTERIA. THE STANDARD 21 GRAM TABLET IS SPECIFIED HERE. DIRECTIONS FOR USE: FOR PLANTING BALLED & BURLAPPED (B&B) TREES AND SHRUBS, MEASURE THE THICKNESS OF THE TRUNK, AND USE ABOUT 1 TABLET (21-G) PER HALF-INCH. PLACE THE TABLETS DIRECTLY NEXT TO THE ROOT BALL, EVENLY DISTRIBUTED AROUND ITS PERIMETER, AT A DEPTH OF ABOUT 4 INCHES. PLANT MATERIAL GUARANTEE NOTES:


1. THE LANDSCAPE CONTRACTOR SHALL GUARANTEE ALL PLANT MATERIAL FOR A PERIOD OF ONE YEAR (1 YR.) FROM APPROVAL OF LANDSCAPE DESIGNER, MUNICIPAL OFFICIAL, OR OWNER/OWNER'S REPRESENTATIVE. LANDSCAPE CONTRACTOR SHALL SUPPLY THE OWNER WITH A MAINTENANCE BOND IN THE AMOUNT OF 10% OF THE VALUE OF THE LANDSCAPE INSTALLATION WHICH WILL BE RELEASED AT THE CONCLUSION OF THE GUARANTEE PERIOD AND ONCE FINAL ACCEPTANCE HAS BEEN GRANTED BY THE PROJECT LANDSCAPE DESIGNER, MUNICIPAL OFFICIAL, OR OWNER/OWNER'S REPRESENTATIVE. 2. THE LANDSCAPE CONTRACTOR SHALL REMOVE AND REPLACE DYING, DEAD, OR DEFECTIVE PLANT MATERIAL AT HIS EXPENSE. THE LANDSCAPE CONTRACTOR SHALL ALSO BE RESPONSIBLE FOR ANY DAMAGES CAUSED BY HIS COMPANY'S OPERATIONS. 3. ALL REPLACEMENT PLANTS SHALL BE OF THE SAME SPECIES AND SIZE AS SPECIFIED ON THE APPROVED OR FINAL PLANT LIST. REPLACEMENTS RESULTING FROM REMOVAL, LOSS, OR DAMAGE DUE TO OCCUPANCY OF THE PROJECT IN ANY PART, VANDALISM, PHYSICAL DAMAGE BY ANIMALS, VEHICLES, ETC., AND LOSSES DUE TO CURTAILMENT OF WATER BY LOCAL AUTHORITIES SHALL BE APPROVED AND PAID FOR BY THE OWNER. 4. THE CONTRACTOR SHALL INSTRUCT THE OWNER AS TO THE PROPER CARE AND MAINTENANCE OF ALL PLANTINGS. 5. THE OWNER SHALL REMOVE AND REPLACE DYING, DEAD, OR DEFECTIVE PLANT MATERIAL ON A YEARLY BASIS AS NEEDED.



GROUND COVER/PERENNIAL/ANNUAL PLANTING DETAIL NOT TO SCALE



(3 ON 1 OR STEEPER) NOT TO SCALE



1. TWO POST SPLIT RAIL RUSTIC FENCE TO BE CEDAR.

2. 2"x4" X 14 GAUGE PVC BLACK VINYL COATED WELDED WIRE FENCE TO BE ATTACHED TO INTERIOR OF SPLIT RAIL FENCEING.


FENCING TO INCLUDE 10' WIDE DOUBLE SWING GATE AROUND STORMWATER MANAGEMENT FACILITIES. 4. ALL FENCING TO BE INSTALLED WITH WELDED WIRE FENCE AROUND STORMWATER MANAGEMENT FACILITIES, ALONG RETAINING WALLS AND AROUND AREAS AS INDICATED ON PLAN. 5. FENCE TO BE INSTALLED AROUND PLAY AREAS WITH BREAK IN FENCE AS INDICATED ON PLAN.

NOT TO SCALE

TOWN OF CHESTER PLANNING BOARD APPROVAL

# ARDEN CONSULTING ENGINEERS, PLLC P.O. BOX 340 MONROE, N.Y. T: 845-782-8114 E: MAM@ARDENCONSULTING.NET

THIS SHEET IS NOT VALID WITHOUT ALL OF THE SHEETS THAT COMPRISE THE S



LIC. NO. 78577

REVISION BY DATE DESCRIPTION

11/13/23 | PER PH & PB COMMENTS

1/17/23 PUBLIC HEARING COMMENTS

3/21/22 DEC EMAIL DATED 03/11/22

12/2/21 PER PB MTG & AF COMMENT LETTER

9/16/21 PREPARATION OF PRELIMINARY PLANS

MM | 2/6/23 | PH CONSULTANT COMMENTS

MM | 8/7/23 | SITE RE-DESIGN

SITE PLAN & LOT LINE COMBINATION FOR DAVIDSON DRIVE HOLDINGS, LLC LAKE STATION ROAD TOWN OF CHESTER, COUNTY OF ORANGE, NY

LANDSCAPING DETAILS

CHECKED:

WARNING- IT IS A VIOLATION OF NEW YORK EDUCATIONAL LAW, SECTION 7209.2, FOR ANY PERSON, UNLESS ACTING UNDER THE DIRECTION OF A LICENSED PROFESSIONAL ENGINEER OR LAND SURVEYOR. TO ALTER THIS DOCUMENT IN ANY WAY. IF ALTERED, THE ALTERING PERSON SHALL COMPLY WITH THE REQUIREMENTS OF NEW YORK EDUCATIONAL LAW, SECTION 7209.2 ONLY MAPS WITH EMBOSSED SEALS ARE GENUINE COPIES OF THE ORIGINAL WORK AND OPINION. MAPS NOT BEARING EMBOSSED SEALS SHOULD NOT BE RELIED UPON SINCE OTHER

THAN EMBOSSED-SEAL COPIES MAY CONTAIN UNAUTHORIZED ND UNDETECTABLE MODIFICATIONS, DELETIONS, ADDITIONS

ND CHANGES.

1. PLANTING BALL - ON B&B MATERIAL, BURLAP AND WIRE BASKET OR OTHER CONTAINER SHALL BE REMOVED FROM THE UPPER HALF OF THE ROOT BALL AND DISPOSED OF.

4. MATERIALS FOR PROTECTION OF PLANTS SHALL BE A COMMERCIALLY AVAILABLE


2. HEIGHT OF PLANTING SAUCER SHALL BE 3".


3. MULCH SHALL BE A MAXIMUM OF 3" DEEP AND TAPERED DOWN TO LEAVE THE ROOT FLARE EXPOSED. WHEN PLANTING ON SLOPES, DOWNHILL SIDE MUST BE STABILIZED APPROPRIATELY OR SEEDING ON DOWNHILL SIDE MAY BE SPECIFIED.


PRODUCT OR SYSTEM FOR SUPPORTING OF TREES. 5. ALL TAGS, LABELS, ETC. SHALL BE REMOVED FROM THE PLANTS. 6. THIS DETAIL SHOWS ONE ABOVE GROUND TREE SUPPORT METHOD. ANY OTHER


METHOD MUST USE COMMERCIALLY AVAILABLE PRODUCTS INSTALLED PER THE MANUFACTURER'S SPECIFICATIONS. 7. THE ROOT FLARE SHALL BE VISIBLE AND LEVEL WITH SURROUNDING SOIL.


COPYRIGHT 2021, ARDEN CONSULTING ENGINEERS, P.L.L.C. - ALL RIGHTS RESERVED

















WATER & SEWER HORIZONTAL SEPARATION NOT TO SCALE


& WATER SEPARATION NOTES

. WHEN IT IS IMPOSSIBLE TO MAINTAIN PROPER HORIZONTAL OR VERTICAL SEPARATION AS SHOWN, THE SEWER SHALL BE DESIGNED AND CONSTRUCTED EQUAL TO THE WATER MAIN, AND SHALL BE PRESSURE TESTED TO ASSURE WATERTIGHTNESS PRIOR TO BACKFILLING. 2. A FULL LENGTH OF BOTH PIPES CROSSING MUST BE CENTERED AT THE CROSSING. 3. BEDDING MATERIAL SHALL BE INCREASED TO 12" BELOW THE LENGTH OF WATER MAIN PIPE FOR 10' ON EITHER SIDE OF THE CROSSING. 4. TWO LAYERS OF CAUTION TRACER TAPE SHALL BE PLACED 18" MINIMUM ABOVE STORM SEWER MAINS.

1. SEPARATION DISTANCE BETWEEN WATER MAINS AND STORM/SEWER MAINS SHALL BE 10' HORIZONTAL AND 18" AT CROSSINGS. THESE SEPARATION DISTANCES MUST BE MAINTAINED UNLESS SPECIFICALLY SHOWN AND INDICATED OTHERWISE ON THE PLANS. THE PREFERRED CROSSING OPTION IS FOR THE WATER MAIN TO BE CONSTRUCTED ABOVE STORM/SEWER MAINS. 2. SEWER MAIN INCLUDES SEWER LATERALS AND STORM DRAIN.

3. WATER MAIN INCLUDES WATER SERVICE LATERALS. 4. DEFLECT WATER MAIN IN AN ARC BENEATH THE SEWER/STORM LINE. DO NOT USE FITTINGS TO DEFLECT THE WATER MAIN.

OVER SEWER SEPARATION NOTES 1. FULL LENGTH OF BOTH PIPES CROSSING MUST BE CENTERED AT THE CROSSING SO THAT PIPE JOINTS WILL BE AS FAR FROM EACH OTHER AS POSSIBLE (10' MIN.). 2. CONTRACTOR SHALL PROVIDE STRUCTURAL SUPPORT FOR EXISTING WATER MAIN OVER THE ENTIRE TRENCH WIDTH TO PREVENT DAMAGE TO THE WATER MAIN. 3. WATER TIGHT JOINTS WHERE WATERLINES ARE CROSSED ABOVE OR BELOW.



1. SYSTEM TO BE INSTALLED IN CONFORMANCE WITH ALL NYSDOH REQUIREMENTS FOR RESIDENTIAL WASTEWATER TREATMENT SYSTEMS.

2. SYSTEM TO MEET ALL SEPARATION REQUIREMENTS. 3. PERFORATED PIPE SHALL BE PLACED SO THAT HOLES ARE FACING 5 & 7 O'CLOCK POSITIONS. 4. TRENCH BOTTOM SHALL BE FLAT. LATERALS SHALL BE INSTALLED AT 1/32" TO 1/16" PER FOOT

FOR GRAVITY FED SYSTEMS & SET NEARLY LEVEL FOR DOSED SYSTEMS. 5. ALL TRENCHES TO HAVE IDENTICAL NUMBER OF ELJEN UNITS.

6. END OF ALL DISTRIBUTION PIPES MUST BE PLUGGED. 7. RAKE SIDES & BOTTOM OF TRENCH PRIOR TO PLACING SAND.

8. DO NOT INSTALL TRENCHES IN WET SOIL. 9. TRENCHES TO BE INSTALLED PARALLEL WITH EXISTING CONTOURS. SPACING SHALL BE A MIN. OF 8 FT. ON CENTER WITH A MINIMUM OF 4 FEET OF UNDISTURBED SOIL BETWEEN TRENCHES. 10. NO SYSTEM IS TO BE CONSTRUCTED ON GROUND WITH A SLOPE IN EXCESS OF 15% GRADE.

11. THE BACKFILL IN THE TRENCHES MUST BE MOUNDED FOR SETTLING. 12. SEE TABLE BELOW FOR ASTM C33 SAND SPECIFICATIONS.


**SPECIFICATIONS** 

CONCRETE MIN. STRENGTH: 4,000 PSI AT 28 DAYS

REINFORCEMENT: 6x6x10GA. WWM

SEIVE	SEIVE SIZE	% PASSING BY	WEIGHT (WET SIEVE)
SIZE	SQ. OPENING	MINIMUM	MAXIMUM
3/8"	9.5 mm	100	100
NO. 4	4.75 mm	95	100
NO. 8	2.36 mm	80	100
NO. 16	1.18 mm	50	85
NO. 30	600 μm	25	60
NO. 50	300 <i>μ</i> m	5	30
NO. 100	150 <i>µ</i> m	0	<10
NO. 200	75 μm	0	<5


ELJEN IN-DRAIN SECTION



PURPOSE OF CLEANOUT LOCATIONS, DISTANCE SHALL BE MEASURED FROM THE FIRST CLEANOUT LOCATED DOWNSTREAM OF THE BUILDING PIPE TO BUILDING LATERAL SEWER CONNECTION, HENCE DOWNSTREAM ALONG THE BUILDING LATERAL SEWER TO THE CENTER OF THE SEWER MAIN LINE

(GENERALLY LOCATED IN THE CENTER OF THE STREET). 2. CLEANOUT LOCATED IN A ROAD, DRIVEWAY OR PARKING AREA SHALL REQUIRE A CAMBELL FOUNDRY #4164 CAST IRON FRAME AND COVER. (OR APPROVED EQUAL).

BUILDING LATERAL SEWER CLEANOUT (C.O.)



1. WELL TO BE INSTALLED IN ACCORDANCE WITH 10NYCRR APPENDIX 5-B & 5-D STANDARDS FOR WATER WELLS. 26. SEPTIC TANKS SHALL BE INSPECTED PERIODICALLY AND PUMPED EVERY 2-3 2. SANITARY WELL SEAL & PITLESS ADAPTER SHALL BE APPROVED BY THE WATER SYSTEMS COUNCIL. 3. GROUTING FOR THE WELL CASING SHALL EXTEND THE ENTIRE DEPTH OR A MINIMUM OF 100'.

24" MIN.

(i.e. ROCK)

GREATER

— WATER

BEARING

FORMATION -

NO SCALE

SANITARY WELL SEAL

- PITLESS ADAPTER

MAASS MODEL J

- GROUT SHOE

MAASS MODEL 6WT OR EQUAL

NATIVE SOIL TO BE

- GRADED TO 3:1 SLOPE

4 FT MIN.(TYP.)

100' MIN. LENGTH - 6" Ø STEEL

COMPLIANCE WITH AWWA STANDARD

MATERIAL OF WELL CASING IN

A-100, LATEST REVISION

FORMATION

TORQUE ARRESTOR

`SET PUMP A MINIMUM

OF 10' FROM BOTTOM

-BOTTOM OF WELL


SUBMERSIBLE

WELL PUMP

WATER TO HOUSE


- EXISTING GRADE


THE LISTED WATER WELL SEPARATION DISTANCES FROM CONTAMINANT SOURCES SHALL BE INCREASED BY 50% WHENEVER AQUIFER WATER ENTERS THE WATER WELL AT LESS THAN 50 FEET BELOW GRADE. IF A 50% INCREASE IN SEPARATION DISTANCES CAN NOT BE ACHIEVED, THEN THE GREATEST POSSIBLE INCREASE IN SEPARATION DISTANCE SHALL BE PROVIDED WITH SUCH ADDITIONAL MEASURES AS NEEDED TO PREVENT CONTAMINATION. SEE ALSO NOTE 1 TO TABLE 1 OF 1. PRIOR TO COMPLETION OF CONSTRUCTION AND/OR ISSUANCE OF A CERTIFICATE OF



TYPICAL ELJEN TRENCH CROSS SECTION

NOT TO SCALE





1. LATERALS TO BE INSTALLED IN CONFORMANCE WITH ALL STATE AND LOCAL DEPARTMENT OF HEALTH REQUIREMENTS

2. ALL SEPARATION DISTANCES TO BE MAINTAINED. 3. 50% EXPANSION AREA REQUIRED FOR ALL NEWLY INSTALLED RESIDENTIAL SYSTEMS. 100% EXPANSION REQUIRED ON COMMERCIAL SYSTEMS.

ELJEN ABSORPTION TRENCH CONFIGURATION

SANITARY NOTES

1. THE DESIGN AND LOCATION OF SANITARY (WATER & SEWER) SYSTEMS SHALL NOT BE CHANGED. 2. ALL WELLS W/I 200' OF THE PROJECT HAVE BEEN LOCATED AND SHOWN ON THE PLANS. 3. TRENCHES SHALL NOT BE INSTALLED IN WET SOIL. THE SIDES AND BOTTOM OF TRENCHES MUST BE RAKED. THE ENDS OF ALL OF THE LATERALS MUST BE CAPPED. 4. THERE SHALL BE NO REGRADING, EXCEPT AS SHOWN ON THE APPROVED PLANS, IN THE AREA OF THE ABSORPTION FIELDS. 5. HEAVY EQUIPMENT SHALL BE KEPT OFF THE AREA OF THE ABSORPTION FIELDS EXCEPT DURING THE ACTUAL CONSTRUCTION. THERE SHALL BE NO UNNECESSARY

MOVEMENT OF CONSTRUCTION EQUIPMENT IN THE ABSORPTION FIELD AREA BEFORE, DURING, OR AFTER CONSTRUCTION. EXTREME CARE MUST BE TAKEN DURING THE ACTUAL CONSTRUCTION SO AS TO AVOID ANY UNDUE COMPACTION THAT COULD RESULT IN A CHANGE OF THE ABSORPTION CAPACITY OF THE SOIL ON WHICH THE 6. THIS SYSTEM WAS NOT DESIGNED TO ACCOMMODATE GARBAGE GRINDERS, JACUZZI TYPE SPA TUBS OVER 100 GALLONS, OR WATER CONDITIONERS. AS SUCH, THESE

ITEMS SHALL NOT BE INSTALLED UNLESS THE SYSTEM IS REDESIGNED TO ACCOUNT FOR THEM AND REAPPROVED BY THE OCDOH. 7. THERE MUST BE AN UNINTERRUPTED POSITIVE SLOPE FROM THE SEPTIC (OR ANY PUMPING OR DOSING CHAMBER) TO THE BUILDING. ALLOWING SEPTIC GASES TO 1" WATER LINE (TYPE "K" COPPER) DISCHARGE THROUGH THE STACK VENT.

8. THE OWNER/APPLICANT SHALL BE PROVIDED WITH A COPY OF THE APPROVED

PLANS AND AN ACCURATE AS-BUILT DRAWING OF ANY EXISTING SANITARY FACILITIES.

THE OWNER/APPLICANT SHALL ALSO BE ADVISED OF ANY ROUTINE OR SPECIAL MAINTENANCE PROCEDURES THAT MAY BE NECESSARY. 9. INDIVIDUAL WELLS AND SEWAGE DISPOSAL SYSTEMS SHALL NO LONGER BE CONSTRUCTED OR USED WHEN PUBLIC FACILITIES BECOME AVAILABLE. CONNECTION TO THE PUBLIC SEWER SYSTEM IS REQUIRED W/I 1 YEAR OF AVAILABILITY. 10. A NEW YORK STATE LICENSED PROFESSIONAL ENGINEER SHALL INSPECT THE SANITARY FACILITIES AT THE TIME OF CONSTRUCTION. THE ENGINEER SHALL CERTIFY TO THE LOCAL CODE ENFORCEMENT OFFICER AND THE OCDOH THAT THE FACILITIES HAVE BEEN INSTALLED IN ACCORDANCE WITH THE APPOVED PLANS AND THAT ANY SEPTIC TANK JOINTS HAVE BEEN SEALED AND TESTED FOR WATER TIGHTNESS. 11. AEROBIC SEPTIC TANK AND PUMP CHAMBER TO BE REINFORCED CONCRETE 12. PIPE FROM HOUSE TO SEPTIC TANK TO BE STRAIGHT

13. NO CELLAR, FOOTING, OR ROOF DRAINS SHALL DISCHARGE INTO SEPTIC TANKS OR

14. THE SEWAGE DISPOSAL SYSTEM SHALL BE DESIGNED, LOCATED AND CONSTRUCTED

TO ALLOW FOR A 50% EXPANSION FOR TILE FIELDS AND 100% EXPANSION FOR ELJEN

SYSTEMS CAPABILITY FOR FUTURE USE. 15. INSTALL TRENCHES PARALLEL TO CONTOURS. 16. DRIVEWAYS AND OTHER STRUCTURES WHICH MAY COMPACT THE SOILS SHALL NOT BE CONSTRUCTED ON TOP OF ABSORPTION FIELD. 17. DIVERSION SWALES TO BE LOCATED UPHILL FROM THE SEWAGE DISPOSAL AREA. THE DIVERSION SWALES ARE TO DIVERT RUNOFF AWAY FROM THE SEWAGE DISPOSAL

DRAIN FIELDS. THERE ARE NO FOOTING DRAINS FOR THE EXISTING SUBJECT

AREA AND THE FUTURE EXPANSION AREA. 18. SEPTIC TANK INLETS TO BE OPPOSITE OUTLETS. 19. ALL ON SITE SANITATION AND WATER SUPPLY FACILITIES SHALL BE BUILT IN ACCORDANCE WITH "WASTE TREATMENT HANDBOOK" INDIVIDUAL HOUSEHOLD SYSTEMS (10 NYCRR 75) OF THE N.Y.S. DEPARTMENT OF HEALTH 1996 DESIGN HANDBOOK. 20. ALL TREES, STUMPS, BRUSH, WEEDS, ETC. SHALL BE CUT TO GRADE AND REMOVED. ALL LEAVES, LIMBS, AND BOULDERS ABOVE GRADE SHALL BE CAREFULLY 21. CONTRACTOR SHALL BE RESPONSIBLE TO LOCATE AND PROPERLY ABANDON EXISTING SEPTIC TANK AND LEACHFIELDS. 22. THE SUBJECT PROPERTY DOES NOT LIE WITHIN A PUBLIC WATERSHED, AND THERE

WILL BE NO CONSTRUCTION ON WATERSHED LANDS. 23. ORANGE COUNTY DEPARTMENT OF HEALTH PLAN APPROVAL IS LIMITED TO 5 YEARS. TIME EXTENSIONS FOR APPROVAL MAY BE GRANTED BY THE ORANGE COUNTY DEPARTMENT OF HEALTH BASED UPON REGULATIONS IN EFFECT AT THAT TIME. A NEW PLAN SYBMISSION MAY BE REQUIRED TO OBTAIN A TIME EXTENSION. 24. ALL ROOF AND FOOTING DRAINS MUST DISCHARGE AWAY FROM SANITARY ABSORPTION FACILITIES. 25. NO LOT IS TO BE FURTHER SUBDIVIDED WITHOUT ORANGE COUNTY DEPARTMENT OF HEALTH REVIEW AND APPROVAL.

27. PUMP STATIONS/DOSING CHAMBERS SHOULD BE INSPECTED PERIODICALLY BY A TRAINED PERSON FOR PROPER OPERATION, INCLUDING HIGH WATER ALARMS, VENTING & ANY PHYSICAL DAMAGE. 28. DISTRIBUTION BOXES SHOULD BE INSPECTED PERIODICALLY TO ASSURE THAT THEY ARE LEVEL AND OPERATING PROPERLY. 29. THE APPROVED PLANS MUST BE FILED WITH THE ORANGE COUNTY CLERK'S OFFICE PRIOR TO OFFERING LOTS FOR SALE AND WITHIN 90 DAYS OF THE LAST

ORANGE COUNTY HEALTH DEPT. AEROBIC UNIT NOTES

EFFECT FOR THE LIFE OF THE AEROBIC UNIT.

APPROVAL OF FINAL PLANS.

OCCUPANCY, A SIGNED SERVICE CONTRACT MUST BE SUBMITTED TO THE ORANGE COUNTY DEPT. OF HEALTH AND THE LOCAL CODE ENFORCEMENT OFFICER. THIS CONTRACT MUST INCLUDE THE FOLLOWING:

A. A MINIMUM DURATION OF 3 YEARS. B. SEMI-ANNUAL SERVICE INSPECTIONS BY A QUALIFIED INDIVIDUAL. C. AT THE TIME ANY AEROBIC UNITS ARE INSTALLED, AND THE AEROBIC UNIT(S) EFFECTIVENESS IS IN QUESTION, SEMI-ANNUAL EFFLUENT TESTING FOR BIOLOGICAL OXYGEN DEMAND (BOD), TOTAL SUSPENDED SOLIDS (TSS), AND ANY OTHER PARAMETERS THAT MAY BE NECESSARY TO SHOW COMPLIANCE NSF STANDARD 40, CLASS 1 (USEPA SECONDARY TREATMENT GUIDELINES). ANALYSES SHALL BE PERFORMED BY A NYS CERTIFIED LABORATORY. D. THE UNIT SHALL BE PUMPED OUT AT LEAST EVERY 3 YEARS, OR MORE FREQUENTLY IF DETERMINED NECESSARY BY THE SERVICE PERSONNEL. E. A NOTATION STATING THAT AFTER THE CONTRACT HAS EXPIRED, IF THE

HOMEOWNER SO CHOOSES, A DIFFERENT QUALIFIED SERVICE PROVIDER CAN BE


2. A SERVICE CONTRACT MEETING ALL REQUIREMENTS OF NOTE #1 MUST BE IN

NOT TO SCALE

AIR ENTRAINMENT: 6%  CONSTRUCTION JOINT: BUTY  PIPE CONNECTION: POLYLOK  WEIGHT = 11,500 LBS  LOAD RATING: 300 PSF	'L RUBBER SEALANT	
5' 8"	NLET NOTE: USE A SANITARY TEE WITH PIP THE NYSDOH REQUIREMENT FOR BAFFLE 16"	E EXTENSION TO MEET BELOW LIQUID LEVEL.
(3)4" DIA. INLETS	4" DIA. PVC (SDR35) 65" 5"x5" 49" LIQUID LEVEL 3" WALLS MIN. 3" 37"	FINISHED GRADE  12"x16" COVER  4" DIA. C.I. OR SCH. 80 PVC FROM BLDG. S=2% MI
TOP VIEW 4" DIA. OUTLET	SIDE VIEW  FIRM UNYIELDING  SUBGRADE	3" MIN. PEA GRAVEL OR SAND
	<u>1,500 GALLON SEPTIC TANK</u>	

REVISION BY DATE DESCRIPTION MM 11/13/23 PER PH & PB COMMENTS MM 8/7/23 SITE RE-DESIGN MM 2/6/23 PH CONSULTANT COMMENTS MM | 1/17/23 | PUBLIC HEARING COMMENTS MM | 3/21/22 | DEC EMAIL DATED 03/11/22 MM | 12/2/21 | PER PB MTG & AF COMMENT LETTER MM 9/16/21 PREPARATION OF PRELIMINARY PLANS MM 5/19/21 REVISION PER PB MTG. & COMMENT LETTERS MM 3/23/21 ROAD LAYOUT REVISION PER PB MTG. THIS SHEET IS NOT VALID WITHOUT ALL OF THE SHEETS THAT COMPRISE THE SI

ARDEN CONSULTING ENGINEERS, PLLC P.O. BOX 340 MONROE, N.Y. T: 845-782-8114 E: MAM@ARDENCONSULTING.NET



SITE PLAN & LOT LINE COMBINATION FOR DAVIDSON DRIVE HOLDINGS, LLC LAKE STATION ROAD TOWN OF CHESTER, COUNTY OF ORANGE, NY

CHECKED:

WARNING- IT IS A VIOLATION OF NEW YORK EDUCATIONAL LAW, SECTION 7209.2, FOR ANY PERSON, UNLESS ACTING UNDER THE DIRECTION OF A LICENSED PROFESSIONAL FNGINFER OR LAND SURVEYOR. TO ALTER THIS DOCUMENT IN ANY WAY. IF ALTERED, THE ALTERING PERSON SHALL COMPLY WITH THE REQUIREMENTS OF NEW YORK EDUCATIONAL LAW, SECTION 7209.2 ONLY MAPS WITH EMBOSSED SEALS ARE GENUINE COPIES OF THE ORIGINAL WORK AND OPINION. MAPS NOT BEARING EMBOSSED SEALS SHOULD NOT BE RELIED UPON SINCE OTHER

THAN EMBOSSED-SEAL COPIES MAY CONTAIN UNAUTHORIZED ND UNDETECTABLE MODIFICATIONS, DELETIONS, ADDITIONS

ND CHANGES


NOT TO SCALE 1. TYPICAL PRECAST CONCRETE SEPTIC TANK, WOODARD CONCRETE PRODUCTS, INC. MODEL ST-1500, OR EQUAL (PROVIDE WATER TIGHT SEAL AT ANY CONSTRUCTION JOINT.) SEPTIC TANK SHALL HAVE A SANITARY TEE W/ GAS DEFLECTOR. ACCESS HATCHES TO SEPTIC TANK IN PARKING LOT MUST BE ACCESSIBLE.

COPYRIGHT 2021, ARDEN CONSULTING ENGINEERS, P.L.L.C. - ALL RIGHTS RESERVED

TOWN OF CHESTER PLANNING BOARD APPROVAL

CHAEL A. MORGANTE, P

SDS DETAILS



# SOIL RESTORATION NOTES:

- DURING PERIODS OF RELATIVELY LOW TO MODERATE SUBSOIL MOISTURE, THE DISTURBED SUBSOILS ARE RETURNED TO ROUGH GRADE AND THE FOLLOWING SOIL RESTORATION STEPS APPLIED: 1) APPLY 3 INCHES OF COMPOST OVER SUBSOIL
- 2) TILL COMPOST INTO SUBSOIL TO A DEPTH OF AT LEAST 12 INCHES USING A CAT-MOUNTED RIPPER. TRACTOR-MOUNTED DISC, OR TILLER, MIXING AND CIRCULATING AIR AND COMPOST INTO SUBSOILS. 3) ROCK-PICK UNTIL UPLIFTED STONE/ROCK MATERIALS OF FOUR INCHES AND LARGER SIZE ARE CLEANED OFF THE SITE 4) APPLY TOPSOIL TO A DEPTH OF SIX INCHES.
- 5) VEGETATE AS REQUIRED BY APPROVED PLAN

**COMPOST SPECIFICATIONS:** 

1) COMPOST SHALL BE AGED, FROM PLANT DERIVED MATERIALS, FREE OF VIABLE WEED SEEDS, HAVE NO VISIBLE FREE WATER OR DUST PRODUCED WHEN HANDLING. PASS THROUGH A HALF INCH SCREEN AND HAVE A PH SUITABLE TO GROW DESIRED PLANTS.


# MAINTENANCE

- 1) SIMPLE MAINTENANCE SHOULD IDENTIFY WHERE SOIL RESTORATION IS APPLIED, WHERE NEWLY RESTORED AREAS ARE/CANNOT BE CLEARED, WHO THE RESPONSIBLE PARTIES ARE TO ENSURE THAT ROUTINE VEGETATION IMPROVEMENTS
- ARE MADE (THINNING, INVASIVE PLANT REMOVAL ETC.) 2) SOIL COMPOST AMENDMENTS WITHIN A FILTER STRIP OR GRASS CHANNEL SHOULD BE LOCATED IN PUBLIC RIGHT OF
- WAY, OR WITHIN A DEDICATED STORMWATER OR DRAINAGE EASEMENT. 3) FIVE YEAR MAINTENANCE OPERATIONS INCLUDES;
- a) INITIAL INSPECTIONS FOR THE FIRST SIX MONTHS (ONCE AFTER EACH STORM GREATER THAN HALF-INCH) b) RESEEDING TO REPAIR BARE OR ERODING AREAS TO ASSURE GRASS STABILIZATION
- É) WATER ONCE EVERY THREE DAYS FOR THE FIRST MONTH. AND THEN PROVIDE A HALF INCH OF WATER PER WEEK DURING THE FIRST YEAR. IRRIGATION PLAN MAY BE ADJUSTED ACCORDING TO THE RAIN EVENT.
- d) FERTILIZATION MAY BE NEEDED IN THE FALL AFTER THE FIRST GROWING SEASON TO INCREASE PLANT VIGOR
- 4) TO ASSIST IN ONGOING MAINTENANCE, PLANTING THE APPROPRIATE GROUND COVER WITH DEEP ROOTS TO MAINTAIN THE SOIL STRUCTURE, AND KEEP THE SITE FREE OF VEHICULAR AND FOOT TRAFFIC OR OTHER WEIGHT LOADS. SOMETIMES IT MAY BE NECESSARY TO DE-THATCH THE TURF EVERY FEW YEARS.


## **OUTLET STRUCTURE NOTES:** . ALL CONCRETE SHALL BE A MINIMUM 4,000 PSI.

- 2. ALL TRASH RACK CONNECTIONS TO OUTLET STRUCTURE SHALL BE ALUMINUM. 3. UPON COMPLETION OF STORMWATER CONSTRUCTION, OWNER SHALL BE RESPONSIBLE FOR MAINTENANCE OF THE DRAINAGE FACILITIES IN ACCORDANCE WITH THE NYSDEC STORMWATER MANAGEMENT DESIGN MANUAL. THESE ITEMS INCLUDE, BUT ARE NOT LIMITED TO:
- A. REMOVAL OF DEBRIS FROM TRASH RACKS B. ROUTINE GRASS CUTTING AROUND INLET PIPES, ORIFICES
- C. SEDIMENT AND GRIT REMOVAL 4. TRASH RACKS FOR OS-1 RIM & RECTANGULAR WEIR PROVIDED BY WOODARDS CONCRETE PRODUCTS, OR EQUAL. 5. PIPES ARE TO BE FLUSH WITH THE INSIDE OF THE OUTLET STRUCTURE WALLS.

- . ALL CONCRETE SHALL BE A MINIMUM 4,000 PSI. . UPON COMPLETION OF INFILTRATION BASINS CONSTRUCTION, OWNER SHALL BE RESPONSIBLE FOR MAINTENANCE OF THE DRAINAGE FACILITIES IN ACCORDANCE WITH THE NYSDEC STORMWATER MANAGEMENT DESIGN MANUAL. THESE ITEMS INCLUDE, BUT ARE NOT LIMITED TO:
- A. REMOVAL OF DEBRIS FROM TRASH RACKS B. ROUTINE GRASS CUTTING AROUND INLET PIPES, ORIFICES C. SEDIMENT AND GRIT REMOVAL
- 3. TRASH RACK IS MANF. BY PLASTIC SOLUTIONS, OR EQUAL. 4. PIPES ARE TO BE FLUSH WITH THE INSIDE OF THE OUTLET STRUCTURE WALLS.



CULVERT PIPE



NOTES:

1. RETAINER GLANDS ARE REQUIRED ON ALL FITTINGS IN ADDITION TO TIE RODS AND THRUST 2. ALL UTILITY TRENCHES WITHIN PAVED AREAS SHALL BE BACKFILLED FULL DEPTH WITH ALL UTILITIES TO BE DEDICATED TO THE TOWN SHALL MEET TOWN OF WALLKILL SPECIFICATIONS.

-8" OF R.O.B. GRAVEL

PRECAST RISER SECT.

TO BRING GRATE TO

OUTLET PIPE - HDPE

SIZE AND INVERTS

BE FIRM AND

UNYIELDING

OR SOLID CONC. BRICKS

\_ MORTAR JOINT

(TYP.)

POINTED TRASH RACK FOR

FLAT TRASH

MADE AS

NEEDED

1/2" HOLES FOR 3/8"

LAI UMINUM⊟

@ SLOPE OF ROAD

SS BOLTS (12"OC SPACING)

RACK H & W

CONCRETE

RIP-RAP PROTECTION SHALL

PAST POINT OF DISCHARGE

EXTEND A MINIMUM OF 6 FEET

OPENINGS UP TO 8" DIAMETER

1-1/2" ANGLE ON TOP

& BOTTOM W/(2) 1/2"

HOLES FOR 3/8" S.S.

SOLID COVER ON

TOP & BOTTOM

1-1/4" X 3/16

PARALLEL BAR

 $\frac{/}{-}$  1.5" X 1.5" X 1/4" ALUM. ANGLE

ALUMINUM TRASH RACK FOR

CONCRETE WEIR

NOT TO SCALE

SLOPE

BOTTOM OF CURB INLET

OF CATCH BASIN.

OVERSIZED HOLES CAST

IN WALLS, PIPE TO BE

SECURELY GROUTED IN

PLACE BY CONTRACTOR

IN FIELD.

THE ENDS OF ALL PIPES SHALL BE CUT OFF FLUSH

WITH THE INSIDE SURFACE

HDPE DRAINAGE PIPE

W/SMOOTH BORE UNLESS

OTHERWISE NOTED ON SITE

SLOPE OF ROAD

4" OC OPENINGS


GRATING W/1-1/4" X


\*CUSTOM SIZED POINTED RACK

1-1/4" X 3/16" --ALUM. PARALLEL BAR

GRATING, 1-1/4"X4"

SPACING






OS-1 OUTLET CONTROL STRUCTURE DETAIL (POCKET POND) NOT TO SCALE

- UNDISTURBED MATERIAL

UNDISTURBED MATERIAL

- LEVEL PEA GRAVEL OR



TOWN OF CHESTER PLANNING BOARD APPROVAL

OWNED PORTION OF THE SYSTEM MUST BE PRIVATELY MAINTAINED. RESPONSIBILITY FOR THE OPERATION AND MAINTENANCE OF THE STORM WATER FACILITIES, INCLUDING PERIODIC REMOVAL AND DISPOSAL OF ACCUMULATED PARTICULATE MATERIAL AND DEBRIS, BUT NOT LIMITED TO THE FOLLOWING: VISUAL INSPECTION OF ALL SYSTEM COMPONENTS AT LEAST TWICE A YEAR: VACUUMING OF ALL STORM SEWER INLETS ONCE EVERY SIX MONTHS (FREQUENCY MAY BE ADJUSTED TO ONCE A YEAR IF FIRST YEAR MAINTENANCE RECORDS INDICATE THAT SEDIMENT AND DEBRIS ACCUMULATION IS INSIGNIFICANT): REVERSE FLUSHING AND VACUUMING IF SYSTEM INSPECTION INDICATE SIGNIFICANT ACCUMULATION OF SEDIMENT IN THE PIPES; AND PERIODIC REMOVAL AND DISPOSAL OF OTHER MATERIAL AND DEBRIS, SHALL REMAIN WITH THE OWNER OR OWNERS

STORMWATER MANAGEMENT FACILITIES SHALL BE REGULARLY MAINTAINED TO ENSURE THEY FUNCTION AT DESIGN

CAPACITY AND TO PREVENT HEALTH HAZARDS ASSOCIATED WITH DEBRIS AND STAGNANT WATER. THE PRIVATELY

STORMWATER FACILITY MAINTENANCE NOTES:

ASSUMED BY A GOVERNMENTAL AGENCY.

AREA AND IN SUCH A MANNER THAT IT WILL NOT ERODE.

IN THE EVENT THAT THE FACILITY BECOMES A DANGER TO PUBLIC SAFETY OR PUBLIC HEALTH, OR IT IS IN NEED OF MAINTENANCE, THE OWNER SHALL EFFECT SUCH MAINTENANCE AND REPAIR OF THE FACILITY IN A MANNER THAT IS APPROVED BY THE TOWN ENGINEER OR HIS DESIGNEE, IF THE OWNER FAILS TO PERFORM SUCH MAINTENANCE AND REPAIR, THE MUNICIPALITY MAY IMMEDIATELY PROCEED TO DO SO AND SHALL BILL THE COST TO THE OWNER.

OF THE PROPERTY, WITH PERMANENT ARRANGEMENTS THAT SHALL PASS TO ANY SUCCESSIVE OWNER, UNLESS

# SEDIMENT TRAP & BASIN CONSTRUCTION SPECIFICATIONS:

1. THE AREA OF THE PROPOSED SEDIMENT BASIN SHALL BE USED AS A SEDIMENT TRAP PRIOR TO FINAL CONSTRUCTION OF THE INFILTRATION BASIN. SEDIMENT TRAP SHALL BE CLEARED, GRUBBED AND STRIPPED OF ANY VEGETATION AND ROOT MAT. INCLUSION OF VEGETATION, ORGANIC MATERIAL, OR FROZEN SOIL IN THE EMBANKMENT, AS WELL AS PLACING OF EMBANKMENT MATERIAL ON A FROZEN SURFACE IS PROHIBITED. 2. THE FILL MATERIAL FOR EMBANKMENTS SHALL BE FREE OF ROOTS OR OTHER WOODY VEGETATION AS WELL AS OVER-SIZED STONES, ROCKS, ORGANIC MATERIAL OR OTHER OBJECTIONABLE MATERIAL. THE EMBANKMENT SHALL BE COMPACTED BY TRAVERSING WITH EQUIPMENT WHILE IT IS BEING CONSTRUCTED IF POSSIBLE. MAXIMUM HEIGHT OF EMBANKMENT SHALL BE FIVE (5) FEET. MEASURED AT CENTERLINE OF EMBANKMENT. PLACE FILL IN LIFTS NOT TO EXCEED 9" AND MACHINE COMPACT. 3. ALL FILL SLOPES SHALL BE 2:1 OR FLATTER, CUT SLOPES 1:1 OR FLATTER.

4. ELEVATION OF THE TOP OF ANY DIKE DIRECTING WATER INTO TRAP MUST EQUAL OR EXCEED HEIGHT OF 5. ENSURE THAT THE SPILLWAY CREST IS LEVEL AND AT LEAST 1.5' BELOW THE TOP OF THE DAM AT ALL POINTS. 6. FILTER CLOTH SHALL BE PLACED OVER THE BOTTOM OF THE OUTLET CHANNEL PRIOR TO PLACEMENT OF STONE SECTIONS OF FABRIC MUST OVERLAP AT LEAST ONE (1) FOOT WITH SECTION NEAREST THE ENTRANCE PLACED ON


TOP. FABRIC SHALL BE EMBEDDED AT LEAST SIX (6) INCHED INTO EXISTING GROUND AT ENTRANCE OF OUTLET 7. STONE USED IN OUTLET CHANNEL SHALL BE FOUR (4) TO EIGHT (8) INCHES (RIP RAP). TO PROVIDE A FILTERING EFFECT. STONE USED FOR SPILLWAY SECTION-CLASS "B" EROSION CONTROL STONE. STONE USED ON INSIDE


SPILLWAY FACE TO CONTROL DRAINAGE - D.O.T. #57 WASHED STONE. A LAYER OF FILTER CLOTH SHALL BE EMBEDDED ONE (1) FOOT WITH SECTION NEAREST ENTRANCE PLACED ON TOP. FABRIC SHALL BE EMBEDDED AT LEAST SIX (6) INCHES INTO EXISTING GROUND AT ENTRANCE OF OUTLET CHANNEL. 8. SEDIMENT SHALL BE REMOVED AND TRAP RESTORED TO ITS ORIGINAL DIMENSIONS WHEN SEDIMENT HAS ACCUMULATED TO 1/2 THE DESIGN DEPTH OF THE TRAP. REMOVED SEDIMENT SHALL BE DEPOSITED IN A SUITABLE

9. THE SEDIMENT TRAP SHALL BE INSPECTED AFTER EACH RAIN AND SHALL BE REPAIRED AS

10. CONSTRUCT EMBANKMENT AND STONE SPILLWAY TO DIMENSIONS, SLOPES AND ELEVATIONS SHOWN ON THE PLAN. 11. CONSTRUCTION OPERATIONS SHALL BE CARRIED OUT IN SUCH A MANNER THAT EROSION AND WATER POLLUTION ARE MINIMIZED. 12. THE STRUCTURE SHALL BE REMOVED AND THE AREA STABILIZED WHEN DRAINAGE AREA HAS BEEN PROPERLY STABILIZED. 13. DRAINAGE AREA FOR THIS PRACTICE IS LIMITED TO 15 ACRES.

15. ENSURE THAT THE TOP OF THE EMBANKMENT AT ALL POINTS IF 0.5' ABOVE NATURAL SURROUNDING GROUND. 16. IMMEDIATELY STABILIZE THE EMBANKMENT AND ALL DISTURBED AREAS AS IN ACCORDANCE WITH THE SPECIFICATIONS SHOWN ON THE GENERAL PLANSET AND EROSION AND SEDIMENT CONTROL PLANS.





# BIORETENTION PLANTING SOIL


IICHAEL A. MORGANTE, P.1

MINIMUM 35 TO 60% SAND, BY VOLUME). THE CLAY CONTENT FOR THESE SOILS SHOULD BE LESS THAN 25% BY VOLUME SOILS SHOULD FALL WITHIN THE SM, OR ML CLASSIFICATIONS OD THE UNIFIED SOIL CLASSIFICATION SYSTEM (USCS). A PERMEABILITY OF AT LEAST 1.0 FEET PER DAY (0 5"/HR) IS REQUIRED (A ROOTS. OR OTHER WOODY MATERIAL OVER I" IN DIAMETER. AND BRUSH OR SEED FROM NOXIOUS WEEDS. PLACEMENT OF THE PLANTING SOIL SHOULD BE IN LIFTS OF IT TO 18", LOOSELY COMPACTED (TAMPED LIGHTLY WITH A DOZER OR BACKHOE BUCKET). THE SPECIFIC CHARACTERISTICS ARE AS FOLLOWS:

PARAMETER	VALUE
PH RANGE	52 TO 7.0
ORGANIC MATTER	1.5 TO 4.0%
MAGNESIUM	35 LBS PER ACRE, MINIMUM
PHOSPHORUS (P <sub>2</sub> O <sub>5</sub> )	75 LBS PER ACRE, MINIMUM
POTASSRA1 (K <sub>2</sub> 0)	85 LBS PER ACRE, MINIMUM
SOLUBLE SALTS	500 ppm
CLAY	10 TO 25%
SILT	30 TO 55%
SAND	35 TO 65%

			<u> </u>	
REVISION	BY	DATE	DESCRIPTION	
9.	ММ	11/13/23	PER PH & PB COMMENTS	
8.	ММ	8/7/23	SITE RE-DESIGN	
7.	ММ	2/6/23	PH CONSULTANT COMMENTS	
6.	ММ	1/17/23	PUBLIC HEARING COMMENTS	
5.	ММ	3/21/22	DEC EMAIL DATED 03/11/22	
4.	ММ	12/2/21	PER PB MTG & AF COMMENT LETTER	
3.	ММ	9/16/21	PREPARATION OF PRELIMINARY PLANS	
2.	ММ	5/19/21	REVISION PER PB MTG. & COMMENT LETTERS	
1.	ММ	3/23/21	ROAD LAYOUT REVISION PER PB MTG.	
THIS S	THIS SHEET IS NOT VALID WITHOUT ALL OF THE SHEETS THAT COMPRISE THE S			

# ARDEN CONSULTING ENGINEERS, PLLC P.O. BOX 340 MONROE, N.Y.



STORMWATER CONSTRUCTION DETAILS

MM CHECKED:

COMPLY WITH THE REQUIREMENTS OF NEW YORK EDUCATIONAL LAW, SECTION 7209.2 ONLY MAPS WITH EMBOSSED SEALS ARE GENUINE COPIES OF THE ORIGINAL WORK AND OPINION. MAPS NOT BEARING EMBOSSED SEALS SHOULD NOT BE RELIED UPON SINCE OTHER THAN EMBOSSED-SEAL COPIES MAY CONTAIN UNAUTHORIZED

WARNING- IT IS A VIOLATION OF NEW YORK EDUCATIONAL

LAW, SECTION 7209.2, FOR ANY PERSON, UNLESS ACTING

ENGINEER OR LAND SURVEYOR, TO ALTER THIS DOCUMENT IN

UNDER THE DIRECTION OF A LICENSED PROFESSIONAL

ANY WAY. IF ALTERED, THE ALTERING PERSON SHALL

ND CHANGES.

TOP OF EMBANKMENT

- 3:1 SIDE SLOPES

TOP OF PROPOSED WEIR INSTALL PERMANENT TURF

& RIP-RAP D50=4"

REINFORCEMENT MATTING

BIORFTENTION WEIR

NOT TO SCALE

COPYRIGHT 2021. ARDEN CONSULTING ENGINEERS, P.L.L.C. - ALL RIGHTS RESERVED

ND UNDETECTABLE MODIFICATIONS, DELETIONS, ADDITIONS

AN ENDANGERED SPECIES IN NEW YORK STATE

Bog Turtle

This area of the Town of Chester near the Davidson Drive Holdings, LLC project on Davidson Drive may contain suitable habitat for the Bog Turtle, which is a New York State Listed Endangered Species. This species is an important part of our ecosystem and it is illegal to kill, harm or harass them. In New York, bog turtles occur in open-canop wet meadows, sedge meadows, and calcareous fens often fed by roundwater and the vegetation always includes various species of sedges  $\Gamma$ his brochure's intent is to educate the public of their potential presence and provide valuable informatio should an encounter occur even though sightings are

This Pamphlet is to be distributed to all construction workers and residents at the project site by the Project Engineer/Biologist after initial training by a **Knowledgeable Wildlife Biologist** 

In case of a sighting, please call Michael Nowicki at 203-910-4716

The NYSDEC Wildlife Office to Report the incident within 24 Hours at 845-256-3098 or Wildlife.R3@dec.ny.gov. Please Provide the location, the project Name, and explanation of incident.





# Fact Sheet

- The bog turtle is New York's smallest turtle, reaching a maximum length of 4.5 inches. A bright yellow or orange blotch on each side of its head and neck are a distinctive feature of this species.
- Mating generally occurs in the spring but autumn mating events are documented. Nesting sites are typically located inside the upper part of an unshaded tussock (a tall, thick bunch of grass).
- Overwintering sites are typically found in densely vegetated areas often in association with tree roots and other submerged structures along streams or near underground
- In New York, the bog turtle is generally found in open, early-successional types of habitats such as wet meadows or open calcareous boggy areas generally dominated by sedges (Carex spp.) or sphagnum moss. Like other cold-blooded or ectothermic species, it requires habitats with a good deal of sunlight for basking and nesting. Plants such as purple loosestrife (Lythrum salicaria) and reed (Phragmites australis) can quickly invade such areas resulting in the loss of basking and nesting habitat.
- Contact the response number on this brochure to have this species identified and relocated from the work area if necessary. A trained state licensed professional will safely relocate the turtle.

## Measure to Take During Encounters

- Measures to take during encounters include: 1. All personnel working at the site will be trained
- to be able to identify, and locate Bog turtles by a knowledgeable biologist. Turtles can only be moved by a qualified biologist with knowledge of Bog and relocation procedures who is also licensed by the NYSDEC to handle Bog turtles.
- It is illegal to take, import, transport, possess, or sell an animal listed as threatened without a 3. If a turtle is seen, stop all work immediately.
- To restart work, written approval is required form the NYSDEC. 4. Contact the contractor in charge and delay work in the area until the turtle has moved safely from the area. Allow the turtle to continue on its way.
- 5. If the turtle does not move along on its own or is found in the barrier fence, contact the following response number to have a trained, NYS licensed professional, safely relocate the turtle (Michael Nowicki at 203-910-4716). 6. Contact the NYSDEC wildlife office to report the incident within 24 hours at 845-256-3098 or wildlife.r3@dec.ny.gov. Please provide the location, the project name, and explanation of
- 7. If the turtle was found within a turtle exclusion fence, work cannot commence until fencing is inspected by and signed off on by a knowledgeable Bog turtle consultant (turtle monitor) and the NYSDEC issues written approval that work can commence. The project sponsor will provide educational

materials for all contractors and residents to

inform of the potential for Bog turtle

encounters and what to do if a turtle is encountered to ensure the animals are not collected or persecuted. 9. If a turtle is found within the temporary barrier fencing, fencing needs to be inspected, repaired, and the area swept and signed off on by the monitor. To restart work, written

approval is required from the department.

# Additional sources of information:

Available from: https://guides.nynhp.org/bog-

New York State Department of Environmental Conservation Bog Turtle Fact Sheet

# **BOG TURTLE EDUCATION** & ENCOUNTER PLAN

For

Davidson Drive Holdings, LLC

**Davidson Drive TOWN OF Chester** 

March 15, 2022

# **Applicant Information:**

- EZ Develop, Inc. Israel Vanchozker Joseph Herskovitz 412 N Main St Monroe, NY 10950
- Note: This report in conjunction with the project plans make up the complete Bog Turtle Education & Encounter Plan.

Prepared by: Michael Nowicki / Ecological Solutions LLC 121 Leon Stocker Drive Stratton, VT 05360

## Davidson Drive Holdings, LLC **Summary of Proposed Conservation Measures for the Bog Turtle**

# CONSTRUCTION

# Worker Training

- At the pre-construction meeting for the project, the designated, knowledgeable biologist (the Biologist) will review the project's Bog Turtle Education and Encounter Plan (BTEEP) with the site Engineer and the Contractors, and will provide them with necessary information to identify and watch out for turtles during construction, and to provide similar
- training to all personnel working on the site during construction. A copy of the BTEEP will be posted on-site at the construction office and copies of the

# **Turtle Barrier Fence**

- Prior to the start of construction at the site, and within the bog turtle hibernation period (between October 31st and March 31st, in accordance with the BTEEP and the project's Construction Sequence, a continuous row of Turtle Barrier Fence (Double Silt Fence) will be installed between the construction area and the wetland/buffer area, in the general location as shown on Drawing 10 and 11 of the site plans.
- The Turtle Barrier Fence will be: 1. Installed in accordance with the Turtle Barrier Fence / Double Silt Fence Detail

BTEEP pamphlet will be provided to personnel as part of their training.

- provided on Drawing 11 of the site plans.
- 2. Buried at the bottom a minimum of 6" into the ground, per the Detail.
- 3. Examined each day by construction workers until construction activities are completed. Any breaches in the silt fencing must be repaired immediately. Work will not re-commence until the permitted person arrives at the site to move the bog turtle to a safe area away from the construction. A worker shall be assigned to monitor the location of the turtle until it is removed from the construction area. In addition, work can not recommence until the NYSDEC provides notice in writing that work can proceed.
- Turtle Barrier Fencing will be maintained until the completion of the project and then completely removed after construction activities are completed.

# **Additional Mitigation Measures during Construction**

- The contractor shall minimize open excavations and structures to avoid turtle pit fall hazards. Excavations completed between April 1st and October 1st shall be backfilled on the same day or a ramp (30-degree angle maximum) will be placed inside the excavation
- to enable turtles to climb out. No construction work or staging of equipment will occur in the wetland or within the potential bog turtle habitat area. Such activities will only be conducted in accordance with the approved site plans.

## Bog Turtle Education & Encounter Plan for Davidson Drive Holdings, LLC

- All stormwater basins are designed to be constructed with interior slopes graded at a
- maximum of 3H:1V, which would allow turtles and other wildlife to escape. • Disturbed areas will be stabilized within 7 days of final grading with permanent cover in the form of vegetation or pavement, as appropriate, in accordance with the Erosion and Sediment Control Notes on Sheet 11 as prepared by Arden Consulting Engineers, PLLC.

# **Procedure for Bog Turtle Encounter and Relocation**

- In the event that a bog turtle is found within the work area:
- 1. All work will cease immediately.

into the wetland.

- 2. Workers are not to touch the turtle. The turtle is not to be collected or persecuted. 3. Turtles can only be moved by a qualified biologist with knowledge of bog turtles
- and relocation procedures, who is licensed by the NYSDEC to handle bog turtles. 4. Workers are to contact the contractor in charge, who will contact a qualified biologist to safely move the bog turtle out of the construction zone and place back

# **Contact Information for Qualified Biologist:** Michael Nowicki at 203-910-4716

- 5. Work will not re-commence until the permitted person arrives at the site to move the bog turtle to a safe area away from the construction, A worker shall be assigned to monitor the location of the turtle until it is removed from the
- construction area. 6. If the turtle is found within the turtle barrier fence, work cannot re-commence until the fencing is inspected by and signed off on by the qualified biologist, and until
- the NYSDEC provides notice in writing that work can proceed. 7. In addition, the New York State Department of Environmental Conservation (NYSDEC) Wildlife Office at 845-256-3098 or Wildlife.R3@dec.ny.gov, and the United States Fish and Wildlife Service (USFWS) New York Field Office at 607-753-9334, must be contacted with 24 hours if a bog turtle is found on the premises. Please provide the location, the project name, and an explanation of the incident.

# POST-CONSTRUCTION - FOR WORKERS, MAINTENANCE STAFF, & the PUBLIC

- All staff will be provided with a copy of the Davidson Drive Holdings, LLC-BTEEP.
- A copy of the Davidson Drive Holdings, LLC-BTEEP will be available on-site at the office. • Copies of the Davidson Drive Holdings, LLC-BTEEP will be provided to maintenance staff as part of their training.

# Bog Turtle Education & Encounter Plan for Davidson Drive Holdings, LLC

# Procedure for Bog Turtle Encounter and Relocation

- In the event that a bog turtle is found on site:
- . Activities will cease immediately (e.g. mowing). 2. Residents and/or staff are not to touch the turtle. The turtle is not to be collected
- or persecuted.
- 3. Turtles can only be moved by a qualified biologist with knowledge of bog turtles and relocation procedures, who is licensed by the NYSDEC to handle bog turtles. 4. Residents or staff should contact a qualified biologist to safely move the bog turtle

## Contact Information for Qualified Biologist: Michael Nowicki at 203-910-4716

back into the wetland.

- 5. Activities will not re-commence until the permitted person arrives at the site to move the bog turtle to a safe area. The resident or staff should monitor the
- location of the turtle until it is removed back to the wetland. 6. In addition, if a bog turtle is found on the premises, the New York State Department of Environmental Conservation (NYSDEC) Wildlife Office at 845-256-3098 or Wildlife.R3@dec.ny.gov, and the United States Fish and Wildlife Service (USFWS) New York Field Office at 607-753-9334, must be contacted with 24 hours. Please provide the location, the project name, and an explanation of the

# Mitigation Measures

- 7. Lawn fertilizer shall be applied at the manufacturer's recommended time of year, but not after December 1st for fall applications or before April 1st for spring
- 8. Lawn fertilizers, pesticides and herbicides shall be applied per the manufacturer's recommendations and shall be applied at the minimum rate needed to accomplish
- 9. Lawn fertilizers, pesticides and herbicides applied or spilled on impervious surfaces, such as driveways or walkways, shall be cleaned up and properly disposed to prevent runoff into drains or waterways.

# FOR ADDITIONAL INFORMATION ON BOG TURTLES, REFER TO THE FOLLOWING

NYSDEC Bog Turtle Fact Sheet (<u>www.dec.ny.gov/animals/7164.html</u>)

• NY Natural Heritage Program Animal Guidance (<a href="www.acris.nynhp.org/guide.php?id=7507">www.acris.nynhp.org/guide.php?id=7507</a>) • US Fish and Wildlife Service New York Field Office Bog Turtle Website (https://www.fws.gov/northeast/nyfo/es/bogturtle.htm)

REVISION	BY	DATE	DESCRIPTION
5.	ММ	11/13/23	PER PH & PB COMMENTS
4.	ММ	8/7/23	SITE RE-DESIGN
3.	ММ	2/6/23	PH CONSULTANT COMMENTS
2.	ММ	1/17/23	PUBLIC HEARING COMMENTS
1.	ММ	3/21/22	DEC EMAIL DATED 03/11/22

THIS SHEET IS NOT VALID WITHOUT ALL OF THE SHEETS THAT COMPRISE THE SI ARDEN CONSULTING ENGINEERS, PLLC

P.O. BOX 340 MONROE, N.Y. T: 845-782-8114 E: MAM@ARDENCONSULTING.NET



SITE PLAN & LOT LINE COMBINATION FOR DAVIDSON DRIVE HOLDINGS, LLC LAKE STATION ROAD TOWN OF CHESTER, COUNTY OF ORANGE, NY

HABITAT PROTECTION PLAN

CHECKED:

WARNING- IT IS A VIOLATION OF NEW YORK EDUCATIONAL LAW, SECTION 7209.2, FOR ANY PERSON, UNLESS ACTING UNDER THE DIRECTION OF A LICENSED PROFESSIONAL ENGINEER OR LAND SURVEYOR, TO ALTER THIS DOCUMENT IN ANY WAY. IF ALTERED, THE ALTERING PERSON SHALL COMPLY WITH THE REQUIREMENTS OF NEW YORK EDUCATIONAL LAW, SECTION 7209.2 ONLY MAPS WITH EMBOSSED SEALS ARE GENUINE COPIES OF THE ORIGINAL WORK AND OPINION. MAPS NOT BEARING EMBOSSED SEALS SHOULD NOT BE RELIED UPON SINCE OTHER THAN EMBOSSED-SEAL COPIES MAY CONTAIN UNAUTHORIZED ND UNDETECTABLE MODIFICATIONS, DELETIONS, ADDITIONS

ND CHANGES.

COPYRIGHT 2021, ARDEN CONSULTING ENGINEERS, P.L.L.C. - ALL RIGHTS RESERVED

TOWN OF CHESTER PLANNING BOARD APPROVAL